DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
COLCHESTER US-2 WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	0.559	F	VR-903R	36	30		THRU/RIGHT ALL TURNS						1		X														
WB	0.519	F	VR-284	30	36		ALL TURNS ===> (45 DEG)						1		X			14.00 13.25											
		F	R3-24	72	18			9.00								2		X									X		
WB	0.439	F	VR-284	30	36		ALL TURNS ===> (45 DEG)						1		X														
		F	R3-24	72	18			9.00								2		12.25 X 12.00									X		
WB	0.432	E	R3-2	24	24		NO LEFT TURN SYMBOL						1		X														
WB	0.427	E	R3-3	48	48		11/06/14	16.00								2		14.25 X 14.00									INSTALL IN MEDIAN AT INTERSECTION OF RTE 2 AND CLAY POINT RD (TH-58)	X		
		F	R3-3	48	48			16.00																			SLIP BASES	X		
WB	0.427	F	R1-1	30	30		STOP						1	X				14.00												
		F	R1-1	30	30			6.25																			EAST OF JUGHANDLE AT INTERSECTION WITH CLAY POINT RD (TH-58)	X		
		E	R5-1	30	30			6.25																			INSTALL ON REVERSE OF STOP SIGN	X		
WB	0.427	G	VR-017	24	30								1	X	~~X~~			14.00											
		G	VR-017	24	30			5.00								1		~~X~~									CLAY POINT RD (TH-58); INSTALL EAST OF JUGHANDLE, WEST OF UTILITY POLE		10	
WB	0.425	E	R5-1	30	30								1	X															
		F	R1-1	30	30			6.25																			IN MEDIAN AT INTERSECTION OF JUGHANDLE AND CLAY POINT RD (TH-58)	X		
SIGN SUMMARY SHEET							SHEET TOTALS	73.75	0.00	0	0	0	~~11~~ 7	0	0	7		~~107.75~~ 105.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	464.5	0.0	22	0	0	52	0	0	43		645.0		0	0.0								

PROJECT NAME: **ALBURGH-COLCHESTER**
PROJECT NUMBER: **STPG SIGN(45)**

FILE NAME: **12 COLCHESTER US2 WB TSS** PLOT DATE: **3/14/2014**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **B. TOOTHAKER** CHECKED **K. KERN**
COLCHESTER WB SHEET 8 SHEET **164** OF **167**