DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 / 2.00 / 2.50 (LB / FT) 1.88	2.42	3.35	TUBULAR STEEL Ø (IN) FOUNDATION	3.00 / 3.50 / 4.00 / 5.00 (LB / FT) 7.60	9.00	10.80	14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	PROJECT SHEET #	STANDARD SHEET #
NB HARTLAND VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.318	A	D3-1	30	5		~~BISCHOFF~~ BISHOFF LN						2 ~~1~~		X											REMOVE THE INDEPENDENTLY INSTALLED STREET NAME SIGN AND POST			
NB	0.339	A	VD2-1	72	10								1 1		X														
		A	VD2-1	72	12		Woodstock 12	6.00								2	11.5'/12.5' X											10	
NB	0.375	A	R2-1	24	30		SPEED LIMIT 40						1		X														
		A	R2-1	24	30			5.00								1	14.0' X											X	
NB	0.426	A	W11-8	30	30			6.25								1	16.0' X									INSTALL 270 FT± NORTH OF THE SPEED LIMIT 40 SIGN AT MP 0.375	X		
NB	0.590	A	W11-6	30	30		0120 1409 0060 SNOWMOBILE CROSSING SYMBOL						1 ~~1~~		X		M.M. REMOVED BADLY FADED			SNOWMOBILE CROSSING SIGN WAS RETAINED DUE TO LIMITED VISIBILITY FOR MOTORISTS.						CROSSING IS CLEARLY VISIBLE AHEAD; SIGN NO LONGER WARRANTED; DISCARD THE MILE MARKER			
NB	0.725	A	R2-1	24	30		SPEED LIMIT 40						1		X														
		A	R2-1	24	30			5.00								1	14.0' X											X	
NB	0.753	A	VD-062B	72	16		OFFICIAL BUSINESS DIRECTIONAL SIGN			1				X												COBB HILL FARMSTAND			
NB	0.807	A	S3-1	30	30		0120 1409 0080 SCHOOL BUS STOP AHEAD						2 ~~1~~		X					M.M. ALSO REMOVED						NO LONGER WARRANTED; DISCARD MILE MARKER NOTE REFERENCE THIS LOCATION FOR THE NEXT SIGN			
NB	0.829	A	W2-2R	30	30			6.25								1	15.0' X									INSTALL 115 FT± NORTH OF THE SIGN REMOVAL AT MP 0.807	X		
		A	W16-8P	30	8		Bowers Rd	1.67																				8	
NB	0.844	A	W1-3MR	30	30		MODIFIED RIGHT REVERSE TURN SYMBOL						1		X											NOTE: BOTH SIGNS ARE INACCURATE			
		A	W13-1P	18	18		25 MPH (PLAQUE)						1																
SIGN SUMMARY SHEET							SHEET TOTALS	30.17	0.00	1	0	0	~~10~~ 8	0	0	6	~~83.0~~ 90.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	339.4	0.0	18	1	1	68	0	0	58	870.0			0	0.0								

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**

FILE NAME: **HARTLAND VT ROUTE 12 NB** PLOT DATE: **8/1/2012**
PROJECT MANAGER: **AMY GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED **AMY GAMBLE**
HARTLAND VT-12 NORTHBOUND 4 SHEET **18** OF **86**