DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB HARTLAND VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	7.699	E	R1-1	30	30		STOP						1		X											THIS LEFT SIDE NB-FACING SIGN IS NO LONGER REQUIRED			
SB	~~7.664~~ 7.682	F	M3-3	24	12		SOUTH						1		X											THIS ASSEMBLY WAS RELOCATED DUE TO A POSTED BRIDGE ASSEMBLY BEING RECENTLY INSTALLED AT SB 7.682.			
		F	M1-5	24	24		VT ROUTE 12						1																
		F	VD2-1	72	12			6.00								2			12.0"/14.0" X							INSTALL THE ASSEMBLY AS SHOWN IN THE SIGN LEGEND; WILL REQUIRE 2.5 INCH POSTS		10	
		F	VD2-1	72	12			6.00																			10	
		F	M3-3	24	12			2.00																		SOUTH, **GREEN ON WHITE**	X		
		F	M1-5	24	24			4.00																		VT ROUTE 12			E-136B
		F	M4-5	24	12			2.00																		TO, **WHITE ON BLUE**	X		
		F	M3-3	24	12			2.00																		SOUTH, **WHITE ON BLUE**	X		
		F	M1-1	24	24			4.00																		INTERSTATE 91	X		
SB	7.640	F	VR-041	24	24		THROUGH WAY BEGINS HERE						1		X											NO LONGER REQUIRED			
		F	R2-1	24	30			5.00								1		15.0" X								X		
SB	7.602	F	R2-1	24	30		SPEED LIMIT 50						1		X														
SB	7.578	E	W3-1	36	36		STOP AHEAD SYMBOL						1		X											THIS LEFT SIDE NB-FACING SIGN IS NO LONGER REQUIRED			
SB	7.561	F	VD2-1	72	10		HARTLAND 8 (CONT. ON NEXT PAGE)						1		X														
							SHEET TOTALS	31.00	0.00	0	0	0	7	0	0	3		~~45.0~~ 41.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	277.6	0.0	12	3	3	64	0	0	49		735.0		0			0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**

FILE NAME: **HARTLAND VT ROUTE 12 SB** PLOT DATE: **8/1/2012**
PROJECT MANAGER: **AMY GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED **AMY GAMBLE**
HARTLAND VT-12 SOUTHBOUND 1 SHEET **26** OF **86**