DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 / 2.00 / 2.50 (LB / FT) 1.88 / 2.42 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 / 3.50 / 4.00 / 5.00 (LB / FT) 7.60 / 9.00 / 10.80 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	PROJECT SHEET #	STANDARD SHEET #
SB HARTLAND VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN														"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	7.561	F	VD2-1	72	10		WINDSOR 13 (CONT.)						1											
SB	6.433	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X						NO LONGER WARRANTED			
SB	5.611	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X						LORDS RD (TH-7)			
		G	W14-1	24	24		DEAD END				I	I	1			I	13.5' X				~~COORDINATE WITH THE STATE ENGINEER TO RETURN THIS SIGN TO THE TOWN~~ THIS SIGN WAS RE-INSTALLED ON A NEW POST.			
		G	unknown	18	24		WATCH FOR CHILDREN PLAYING						1								COORDINATE WITH THE STATE ENGINEER TO RETURN THIS SIGN TO THE TOWN			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1	13.5' X						6	
SB	5.603	F	D3-1	30	5		LORDS RD						1		X						LORDS RD (TH-7)			
		H	R1-1	30	30		STOP						1											
		F	D3-1	36	12		Lords Rd	3.00								1	14.5' X				INSTALL THE STREET SIGN ON TOP OF THE POST PERPENDICULAR TO THE STOP SIGN		11	
		H	R1-1	30	30		STOP	6.25														X		
SB	5.461	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X						NO LONGER WARRANTED			
SB	5.026	F	W2-2	30	30			6.25								1	15.5' X				INSTALL 380 FT± IN ADVANCE OF THE JCT WITH DAMON RD	X		
		F	W16-8P	30	8		Damon Rd	1.67															8	
SB	4.954	G	VR-017	24	30								1		X						DAMON RD ~~(TH NUMBER UNKNOWN)~~ 26			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1	14.0' X						6	
SIGN SUMMARY SHEET							SHEET TOTALS	27.17	0.00	0	~~1~~ 0	~~1~~ 0	9	0	0	~~5~~ 4	~~71.0~~ 60.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	277.6	0.0	12	3	3	64	0	0	49	735.0		0	0.0							

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**

FILE NAME: **HARTLAND VT ROUTE 12 SB** PLOT DATE: **8/1/2012**
PROJECT MANAGER: **AMY GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED: **AMY GAMBLE**
HARTLAND VT-12 SOUTHBOUND 2 SHEET **27** OF **85**