DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 2.00 2.50 (LB / FT)			TUBULAR STEEL Ø (IN) FOUNDATION	3.00 3.50 4.00 5.00 (LB / FT)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	PROJECT SHEET #	STANDARD SHEET #
																	1.88	2.42	3.35		7.60	9.00	10.80	14.60					
SB HARTLAND VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	4.388	F	W7-1	30	30			6.25								1		14.0' X								INSTALL 25 FT± NORTH OF (IN ADVANCE OF) THE HIDDEN DRIVES SIGN ASSEMBLY AT MP 4.383	X		
SB	4.383	F	VW-133R	30	30		HIDDEN DRIVES RIGHT				1		1													NOTE LOCATION AS REFERENCE FOR THE NEXT SIGN			
		F	W16-4P	24	18		NEXT 600 FT (PLAQUE)						1																
SB	4.347	F	VW-133R	30	30		HIDDEN DRIVES RIGHT					1				1		15.0' X								SALVAGE THIS SIGN TO 190 FT± SOUTH OF THE PREVIOUS POSITION AT MP 4.383			
SB	3.797	F	W1-5L	30	30			6.25								1		14.5' X								INSTALL 125 FT± NORTH OF (IN ADVANCE OF) THE RIGHT REVERSE CURVE SIGN AT MP 3.773	X		
SB	3.773	F	W1-4R	30	30		0120 1409 0380 RIGHT REVERSE CURVE						1		X	1													
SB	1.930	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						2 ~~1~~		X					ON 4/19/13 THIS SIGN WAS RE-INSTALLED BY A LOCAL RESIDENT DIRECTLY AFFECTED BY THIS SIGN.							BOTH SIGNS NO LONGER WARRANTED			
		F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1							IT WAS REMOVED BY THE CONTRACTOR AGAIN ON 6/28/13. PAY FOR 2 REMOVALS.							NOTE LOCATION AS REFERENCE FOR THE NEXT SIGN			
SB	1.877	F	W1-2L	30	30			6.25								1		14.5' X								INSTALL 280 FT± SOUTH OF THE SIGN REMOVALS AT MP 1.930	X		
SB	1.782	F	R2-5A	24	30		REDUCED SPEED AHEAD						1		X											REMOVE THIS SIGN; FROM FURTHER AHEAD AT MP 1.729, SALVAGE THE TWO BUSINESS SIGNS TO HERE			
		F	VD-062B	72	16		SNOWMOBILE CROSSING (HINGED SIGN) OFFICIAL BUSINESS DIRECTIONAL SIGN				1	1	1			2	16.0'/18.0' X									SKUNK HOLLOW TAVERN			
		F	VD-062B	72	16		OFFICIAL BUSINESS DIRECTIONAL SIGN					1														COBB HILL FARMSTAND			
SB	1.729	F	VD-062B	72	16		OFFICIAL BUSINESS DIRECTIONAL SIGN				1		1		X											SKUNK HOLLOW TAVERN			
		F	VD-062B	72	16		OFFICIAL BUSINESS DIRECTIONAL SIGN				1		1													COBB HILL FARMSTAND			
		F	W3-5	36	36		SPEED LIMIT 35	9.00								2	14.5'/14.5' X								INSTALL THE NEW SPEED REDUCTION SIGN HERE, THE BUSINESS SIGNS TO BE SALVAGED NORTH TO MP 1.782.	X		
SIGN SUMMARY SHEET							SHEET TOTALS	27.75	0.00	0	~~4~~ 3	~~4~~ 3	~~11~~ 6	0	0	8		~~121.0~~ 120.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	277.6	0.0	12	3	3	64	0	0	49		735.0		0		0.0							

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**
FILE NAME: **HARTLAND VT ROUTE 12 SB**
PROJECT MANAGER: **AMY GAMBLE**
DESIGNED BY: **M. MILLER**
PLOT DATE: **8/1/2012**
DRAWN BY: **M. MILLER**
CHECKED **AMY GAMBLE**
HARTLAND VT-12 SOUTHBOUND 4
SHEET **29** OF **85**