DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB HARTLAND VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	1.673	F	VD-018	30	18		HARTLAND FOUR CORS. HARTLAND 2						1		X										NOTE LOCATION AS REFERENCE FOR THE NEXT SIGN			
SB	1.654	F	VD-018	30	18		Hartland Four Corners Hartland 2	3.75								1		14.0' X							INSTALL 100 FT± SOUTH OF THE FORMER VILLAGE SIGN REMOVED AT MP 1.673		14	
SB	~~1.600~~ 1.602	F	W1-10aL	36	36			9.00								2		14.0'/14.0' X			SIGN REPLACED AT ORIGINAL LOCATION DUE TO SNOWMOBILE X-ING.				~~INSTALL 35 FT± NORTH OF (IN ADVANCE OF) THE SIGN ASSEMBLY AT MP 1.602~~	X		
SB	1.602	F	W1-2ML	30	30		MODIFIED LEFT CURVE INTERSECTION						1		X													
		F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1												NO LONGER WARRANTED			
SB	1.564	F	R2-1	24	30								1		X													
		F	R2-1	30	36		SPEED LIMIT 35	7.50								1		14.0' X							NOTE: NEW SIGN IS LARGER	X		
SB	1.481	G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS NOTICE WEIGHT LIMIT						1		X										BROWNSVILLE RD (TH-1)			
		G	VR-017	24	30			5.00			I	I	I			1		14.0' X									6	
SB	1.468	F	D3-1	54	12		Brownsville Rd			1				X											BROWNSVILLE RD (TH-1)			
		H	R1-1	30	30		0120 1409 0148 STOP			I 1															BOTH SIGNS AS-NEW			
SB	1.452	F	M3-3	18	9		SOUTH						1		X										BOTH SIGNS ARE ANCIENT AND HIDDEN IN THE TREES			
		F	M1-6	24	24		VERMONT 12						1												OLD STYLE BLACK ON WHITE DESIGN			
SB	1.433	F	M3-3	24	12		SOUTH						1		X													
		F	M1-5	24	24		VT ROUTE 12 (CONT. ON NEXT PAGE)						1															
							SHEET TOTALS	25.25 SF	0.00 SF	2 EA	I ~~0~~ EA	I ~~0~~ EA	I0 ~~0~~ EA	0 EA	0 EA	5 EA		~~70.0~~ ~~75.0~~ FT	0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	277.6	0.0	12	3	3	64	0	0	49		735.0	0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**

FILE NAME: **HARTLAND VT ROUTE 12 SB**
PROJECT MANAGER: **AMY GAMBLE**
DESIGNED BY: **M. MILLER**
HARTLAND VT-12 SOUTHBOUND 5

PLOT DATE: **8/1/2012**
DRAWN BY: **M. MILLER**
CHECKED: **AMY GAMBLE**
SHEET **30** OF **85**