DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB HARTLAND VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	0.198	F	M1-4	24	24		US ROUTE 5 (CONT.)						1																
		F	M2-1	21	15			2.19								0 ~~1~~		0 ~~X~~		SEE PREVIOUS SHEET					JCT, **BLACK ON WHITE**	X		
		F	M1-4	24	24			4.00																		US ROUTE 5	X		
SB	0.162	F	R6-1L	36	12		<--- ONE WAY			1				X															
		E	R6-1R	36	12		ONE WAY --->			1																THIS SIGN FACES NB TRAFFIC			
SB	0.160	F	W11-2	30	30		PEDESTRIAN SYMBOL						1		X														
		F	W16-7PL	24	12		DIAGONAL ARROW DOWN LEFT						1																
SB	0.159	F	W11-2	30	30	FYG		6.25								1		16.0' X								~~INSTALL THE NEW SIGNS 5 FT. SOUTH OF THE PREVIOUS POSITION~~	X		
		F	W16-7PL	24	12	FYG		2.00																			X		
SB	0.150	F	R6-1L	36	12		<--- ONE WAY			1				X															
		E	R6-1R	36	12		ONE WAY --->			1																THIS SIGN FACES NB TRAFFIC			
SB	0.111	F	W3-1	36	36		STOP AHEAD SYMBOL			1				X															
SB	0.078	F	VD1-1A	72	12		White River Jct. 10	6.00								2		13.0'/13.0' X								INSTALL 10 FT± NORTH OF THE EXISTING DESTINATION SIGNS AT MP 0.076		10	
		F	VD1-1A	72	12		Windsor 5	6.00																				9	
SB	0.076	F	VD1-1A	72	10		^UP WHITE RIVER JCT 10 (CONT. ON NEXT PAGE)						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	26.44	0.00	5	0	0	4	0	0	3 ~~4~~		42.0 ~~60.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	277.6	0.0	12	3	3	64	0	0	49		735.0		0		0.0							

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**
FILE NAME: **HARTLAND VT ROUTE 12 SB**
PROJECT MANAGER: **AMY GAMBLE**
DESIGNED BY: **M. MILLER**
HARTLAND VT-12 SOUTHBOUND 8
PLOT DATE: **8/1/2012**
DRAWN BY: **M. MILLER**
CHECKED: **AMY GAMBLE**
SHEET **33** OF **85**