DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 / 2.00 / 2.50 (LB / FT)	TUBULAR STEEL Ø (IN) 3.00 / 3.50 / 4.00 / 5.00 (LB / FT)	FOUNDATION	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB POMFRET VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN														"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.353	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		X						NOTE LOCATION AS REFERENCE FOR THE NEXT SIGN			
NB	0.391	A	W1-4R	30	30			6.25								1	14.0' X				INSTALL ~~200~~ 150 FT± NORTH OF THE REMOVAL AT MP 0.353	X		
NB	0.783	A	W1-5R	30	30		RIGHT WINDING CURVES						1		X						NOTE LOCATION AS REFERENCE FOR THE NEXT SIGN			
NB	0.802	A	W1-5R	30	30		0120 1413 0080	6.25			1	1	1			1	16.0' X				INSTALL 100 FT± NORTH OF THE REMOVAL AT MP 0.783	X		
							SHEET TOTALS	12.50	0.00	0	~~1~~ 0	~~1~~ 0	~~3~~ 2	0	0	2	30.0	0	0.0	0.0	0.0	0.0			
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	EA	LB	LB	LB	LB			
							TOWN DIRECTIONAL TOTALS	12.5	0.0	0	0	0	2	0	0	2	30.0	0	0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**

FILE NAME: **POMFRET VT ROUTE 12 NB**
PROJECT MANAGER: **AMY GAMBLE**
DESIGNED BY: **M. MILLER**
POMFRET VT-12 NORTHBOUND 1

PLOT DATE: **5/24/2012**
DRAWN BY: **M. MILLER**
CHECKED **AMY GAMBLE**
SHEET **45** OF **85**