DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB BARNARD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	5.175	A	D3-1	54	12		Davis Rd TH-72	4.50								2	14.0'/14.0' X									INSTALL INDEPENDENTLY ON TWO POSTS BEHIND RAIL ON THE STOP SIGN SIDE OF THE INTERSECTION		12	
NB	5.441	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X											DAVIS RD (TH-72) (NORTHERLY JCT, SOUTHERLY APPROACH)			
		C	VR-017	24	30			5.00								1	14.0' X									INSTALL THE NEW SIGN AT A POINT JUST BEYOND THE JCT OF THE TWO APPROACHES OF TH-72		6	
NB	5.447	D	R1-1	30	30		STOP						1		X											DAVIS RD (TH-72) (NORTHERLY JCT, SOUTHERLY APPROACH)			
		D	R1-1	30	30			6.25								1	11.0' X										X		
NB	5.451	A	D3-1	54	12		Davis Rd TH-72	4.50								2	14.0'/14.0' X									INSTALL THE STEET SIGN PERPENDICULAR TO ROUTE 12 MIDWAYs BETWEEN THE TWO APPROACHES TO DAVIS RD		12	
NB	5.455	A	D3-1	30	6		DAVIS RD TH72						1		X											REMOVE THE INDEPENDENLY INSTALLED STREET SIGN ADJACENT TO THE LEGAL LOAD LIMIT SIGN			
NB	5.455	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X											DAVIS RD (TH-72) (NORTHERLY JCT, NORTHERLY APPROACH)			
NB	5.465	D	R1-1	30	30		STOP						1		X											DAVIS RD (TH-72) (NORTHERLY JCT, NORTHERLY APPROACH)			
		D	R1-1	30	30			6.25								1	14.0' X										X		
NB	6.130	A	D3-1	36	6		BLACKMER RD TH-30						1		X					THE NEW STREET SIGN WAS FOUND DAMAGED BY VANDALS AT FINAL INSPECTION. IT WAS REPLACED.						INSTALLED INDEPENDENTLY ON THE LEGAL LOAD LIMIT SIGN SIDE OF THE INTERSECTION			
		A	D3-1	66	12		Blackmer Rd TH-30	5.50 5.50					1			2	15.0'/15.0' X									INSTALL IN THE SAME POSITION AS THE REMOVAL		12	
NB	6.132	C	VR-017	24	30		LEGAL LOAD LIMIT 16,000 POUNDS						1		X											BLACKMER RD (TH-30)			
		C	VR-017	24	30			5.00								1	14.0' X											6	
NB	6.140	D	R1-1	30	30		STOP (CONT. ON NEXT PAGE)						1		X											BLACKMER RD (TH-30)			
SIGN SUMMARY SHEET							SHEET TOTALS	42.50 ~~37.00~~	0.00	0	0	0	9 ~~8~~	0	0	10	139.0 ~~150.0~~			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	322.2	0.0	6	2	2	59	0	0	65	975.0			0	0.0								

PROJECT NAME: HARTLAND-BETHEL
PROJECT NUMBER: STPG SIGN (40)

FILE NAME: BARNARD VT ROUTE 12 NB
PROJECT MANAGER: AMY GAMBLE
DESIGNED BY: M. MILLER
BARNARD VT-12 NORTHBOUND 6

PLOT DATE: 8/1/2012
DRAWN BY: M. MILLER
CHECKED: AMY GAMBLE
SHEET 53 OF 85