DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 / 2.00 / 2.50 (LB / FT) 1.88 / 2.42 / 3.35	TUBULAR STEEL Ø (IN) 3.00 / 3.50 / 4.00 / 5.00 (LB / FT) 7.60 / 9.00 / 10.80 / 14.60	FOUNDATION	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	PROJECT SHEET #	STANDARD SHEET #
NB BARNARD VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN														"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	8.642	C	VR-017	24	30		LOCAL USE LIMIT 24,000 POUNDS (CONT.)	5.00								1	14.0' X						6	
NB	8.648	D	R1-1	30	30		STOP						0 ~~1~~		0 ~~X~~				MISSING.		(TH-66)			
		A	D3-1	24	12		~~TH-66~~ NOT INSTALLED - SEE NOTE.	2.00								~~1~~ 2	14.0'/14.0' X		THIS SIGN WAS CHANGED TO HAMBSCH FARM RD. SEE SHEET #56.		INSTALL THE STREET SIGN ON TOP OF THE POST, PERPENDICULAR TO THE STOP SIGN		12	
		D	R1-1	30	30		STOP	6.25											PAY CONTRACTOR FOR TH-66 SIGN.			X		
NB	8.721	A	W1-2L	30	30								1		X									
		A	W1-2L	30	30			6.25								1	15.0' X					X		
NB	8.878	A	W1-2R	30	30			6.25								1	15.0' X				INSTALL 65 FT± SOUTH OF (IN ADVANCE OF) THE SIGN ASSEMBLY AT MP 8.890	X		
NB	8.890	A	W1-10R	30	30		MODIFIED RIGHT CURVE						1		X									
		A	W16-8aP	24	18		RHAODES HILL (PLAQUE)						1								NOTE LOCATION AS REFERENCE FOR THE NEXT SIGN			
NB	8.918	A	W2-2R	30	30			6.25								1	15.0' X				INSTALL BEHIND RAIL 150 FT± NORTH OF THE REMOVAL AT MP 8.890	X		
		A	W16-8aP	24	15		Rhoades Hill	2.50															8	
NB	8.954	A	OM3-R	12	36								1		X									
		A	OM3-R	12	36			3.00								1	11.0' X				INSTALL BEHIND RAIL AT 4 FT VERTICAL CLEARANCE	X		
NB	8.972	B	OM3-L	12	36								1		X						THIS SIGN FACES SB TRAFFIC			
		B	OM3-L	12	36			3.00								1	11.0' X				INSTALL BEHIND RAIL AT 4 FT VERTICAL CLEARANCE	X		
							SHEET TOTALS	40.50	0.00	0	0	0	5 ~~6~~	0	0	~~8~~ 7	109.0 ~~105.0~~		0	0.0	0.0	0.0	0.0			
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB			
							TOWN DIRECTIONAL TOTALS	322.2	0.0	6	2	2	59	0	0	65	975.0		0	0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: HARTLAND-BETHEL
PROJECT NUMBER: STPG SIGN (40)

FILE NAME: BARNARD VT ROUTE 12 NB
PROJECT MANAGER: AMY GAMBLE
DESIGNED BY: M. MILLER
BARNARD VT-12 NORTHBOUND 8

PLOT DATE: 8/1/2012
DRAWN BY: M. MILLER
CHECKED: AMY GAMBLE
SHEET 55 OF 85