DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 / 2.00 / 2.50 (LB / FT) 1.88 / 2.42 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 / 3.50 / 4.00 / 5.00 (LB / FT) 7.60 / 9.00 / 10.80 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	PROJECT SHEET #	STANDARD SHEET #
NB BETHEL VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN														"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	3.061	A	W13-1P	18	18		35-MPH (PLAQUE) (CONT.)						1											
		A	W13-1P	18	18			2.25													INSTALL THE NEW PLAQUE IN THE SAME POSITION AS THE REMOVED 35-MPH PLAQUE	X		
NB	3.213	A	S3-1	36	36		SCHOOL BUS STOP AHEAD (TEXT)						1		X									
		A	S3-1	36	36	FYG		9.00								2	15.0'/15.0' X					X		
NB	3.532	A	D3-1	30	5		STAFFORD MEADOWS LN						1						OLD SIGN WAS TAKEN TO THE TOWN ROAD CREW.		STAFFORD MEADOWS LN (TH-92); **SIGN AND POST MISSING**			
		A	D3-1	66	12			5.50								2	11.0'/11.0' X				DUE TO SIGN WIDTH AND SKEW OF THE INTERSECTION, INSTALL ON THE LEGAL LOAD LIMIT SIGN SIDE OF TH-92		13	
NB	3.533	C	VR-017	24	30								~~1~~		X				OLD SIGN AND POST MISSING		STAFFORD MEADOWS LN (TH-92)			
		C	VR-017	24	30			5.00								1	14.0' X						6	
NB	3.542	D	R1-1	30	30								1		X						STAFFORD MEADOWS LN (TH-92)			
		D	R1-1	30	30		0120 1404 0354	6.25			I	I	I			1	14.0' X					X		
NB	3.728	A	W1-2L	30	30		LEFT CURVE						1		X						NOTE LOCATION AS REFERENCE FOR THE NEXT SIGN			
		A	W13-1P	18	18		35-MPH (PLAQUE)						1											
NB	3.778	A	W5-2	36	36			9.00								2	15.0'/15.0' X				INSTALL 265 FT± NORTH OF THE SIGNS REMOVED AT MP 3.728	X		
NB	3.797	A	W5-2	30	30		0120 1404 0380 NARROW BRIDGE						1		X						REMOVE BOTH THE RIGHT AND LEFT-SIDE NARROW BRIDGE SIGNS AT THE SAME TIME (NEXT ENTRY)			
SB	3.797	E	W5-2	30	30		NARROW BRIDGE						1		X						**FACES NB TRAFFIC ADJACENT TO THE SB LANE**			
							SHEET TOTALS	37.00	0.00	0	~~1~~ 0	~~1~~ 0	~~10~~ 0	0	0	8	~~110.0~~ ~~20.0~~		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	210.3	0.0	27	1	1	38	0	0	45	675.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**

FILE NAME: **BETHEL VT ROUTE 12 NB**
PROJECT MANAGER: **AMY GAMBLE**
DESIGNED BY: **M. MILLER**
BETHEL VT-12 NORTHBOUND 3

PLOT DATE: **8/1/2012**
DRAWN BY: **M. MILLER**
CHECKED: **AMY GAMBLE**
SHEET **71** OF **85**