DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB BETHEL VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	5.563	A	W16-2	24	18		500 FEET (PLAQUE) (CONT.)						1															
		A	W1-4R	30	30			6.25								1		15.0' X									X	
		A	W13-1P	24	24		35 MPH	4.00																			X	
NB	5.597	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		X													
		A	W13-1P	18	18		35-MPH (PLAQUE)						1															
		A	VW-054R	30	30		HIDDEN DRIVE RIGHT 0120 1404 0560	6.25			1	1	1			1		15.0' X										7
NB	5.726	A	W1-6L	48	24								1		X													
		A	W1-6L	48	24			8.00								2		15.0'/15.0' X									X	
NB	6.175	A	W1-5R	30	30		RIGHT WINDING ROAD SYMBOL						1		X											NOTE LOCATION AS REFERENCE FOR THE NEXT SIGN			
		A	W13-1P	18	18		35-MPH (PLAQUE)						1															
NB	6.232	A	W1-4R	30	30			6.25								1		15.0' X								INSTALL ~~300~~ 275 FT± NORTH OF THE SIGNS REMOVED AT MP 6.175	X	
		A	W13-1P	24	24		35 MPH	4.00																			X	
NB	6.439	A	W1-6L	48	24								1		X													
		A	W1-6L	48	24			8.00								2		~~16.0'~~/17.0' X									X	
NB	6.441	B	W1-6R	48	24		LARGE ARROW RIGHT (CONT. ON NEXT PAGE)						1		X													
SIGN SUMMARY SHEET							SHEET TOTALS	42.75 SF	0.00 SF	0 EA	~~1~~ 0 EA	~~1~~ 0 EA	~~9~~ 0 EA	0 EA	0 EA	7 EA		~~108.0~~ 105.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	210.3	0.0	27	1	1	38	0	0	45		675.0		0	0.0								

PROJECT NAME: HARTLAND-BETHEL
PROJECT NUMBER: ~~STPG SIGN (40)~~

FILE NAME: BETHEL VT ROUTE 12 NB
PROJECT MANAGER: AMY GAMBLE
DESIGNED BY: M. MILLER
BETHEL VT-12 NORTHBOUND 7

PLOT DATE: 8/1/2012
DRAWN BY: M. MILLER
CHECKED: AMY GAMBLE
SHEET: 75 OF 85