DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB BETHEL VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	6.544	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
		F	W1-5R	30	30		RIGHT WINDING CURVES SYMBOL						1																
		F	W13-1P	18	18		35-MPH (PLAQUE)						1																
		F	W1-5R	30	30			6.25								1			14.0' X									X	
		F	W13-1P	24	24			4.00																				X	
SB	6.500	F	VW-054R	30	30			6.25								1			14.0' X								INSTALL 230 FT± SOUTH OF THE SIGNS AT MP 6.544		7	
SB	5.930	F	VW-054R	30	30		HIDDEN DRIVE RIGHT			1				X															
SB	5.863	F	W1-4L	30	30		LEFT REVERSE CURVE				1		1		X												TO BE SALVAGED 135 FT± SOUTH			
		F	W13-1P	18	18		40-MPH (PLAQUE)				1		1																
SB	5.837	F	W1-4L	30	30		LEFT REVERSE CURVE					1				1			15.0' X								SALVAGE TO BEHIND RAIL 135 FT± SOUTH OF THE PREVIOUS POSITION AT MP 5.863			
		F	W13-1P	18	18		40-MPH (PLAQUE)					1																	
SB	5.790	F	VW-060	30	30		HIDDEN DRIVES				1		1		X												SALVAGE THIS SIGN ON TO A NEW POST			
		F	VW-060	30	30		HIDDEN DRIVES					1				1			14.0' X										
SB	5.655	F	W2-2R	30	30		RIGHT SIDE ROAD				1		1		X												TO BE SALVAGED 150 FT± SOUTH			
		F	W16-8A	24	18		GILEAD BROOK RD (PLAQUE)				1		1																
SIGN SUMMARY SHEET							SHEET TOTALS	16.50	0.00	1	5	3	8	0	0	4			~~57.0~~ ~~80.0~~	0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT	EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	237.8	0.0	8	9	9	52	0	0	53			795.0	0			0.0					

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**
FILE NAME: **BETHEL VT ROUTE 12 SB** PLOT DATE: **8/1/2012**
PROJECT MANAGER: **AMY GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED **AMY GAMBLE**
BETHEL VT-12 SOUTHBOUND 1 SHEET **77** OF **85**