DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 / 2.00 / 2.50 (LB / FT)	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 / 3.50 / 4.00 / 5.00 (LB / FT)	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	PROJECT SHEET #	STANDARD SHEET #
SB BETHEL VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN														"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	3.419	F	W1-5L	30	30			6.25								1	17.0' X				INSTALL BEHIND RAIL 130 FT± SOUTH OF THE SIGNS REMOVED AT MP 3.444	X		
		F	W13-1P	18	18			2.25														X		
SB	3.332	F	D3-1	30	5								1		X						WATERSHED RD (TH-38)			
		F	D3-1	54	12			4.50								2	14.0'/14.0' X				DUE TO SIGN WIDTH, INSTALL INDEPENDENTLY ON THE LEGAL LOAD LIMIT SIGN SIDE OF TH-38		13	
SB	3.332	G	VR-017	24	30		LEGAL LOAD LIMIT 16,000 POUNDS						1		X						WATERSHED RD (TH-38)			
		H	R1-1	30	30		STOP						1								LEFT-SIDE STOP SIGN FOR TH-38 IS NO LONGER WARRANTED			
		G	VR-017	24	30			5.00								1	14.0' X						6	
SB	3.320	H	R1-1	30	30								1		X						WATERSHED RD (TH-38)			
		H	R1-1	30	30		0120 1404 0329	6.25			1	1	1			1	14.0' X					X		
SB	3.296	F	VW-054L	30	30		HIDDEN DRIVE LEFT						1		X						NOTE LOCATION AS REFERENCE FOR THE NEXT ASSEMBLY			
SB	3.277	F	VW-054L	30	30			6.25								1	13.0' X				INSTALL 100 FT± SOUTH OF THE SIGN REMOVED AT MP 3.296		7	
SB	2.963	F	S3-1	36	36		SCHOOL BUS STOP AHEAD (TEXT)						1		X									
		F	S3-1	36	36	FYG		9.00								2	15.0'/16.0' X					X		
SB	2.918	F	W1-2L	30	30		LEFT CURVE				1		1		X									
		F	W1-2L	30	30		LEFT CURVE					1				1	15.0' X				SALVAGE THIS SIGN ONTO A NEW POST			
SIGN SUMMARY SHEET							SHEET TOTALS	39.50	0.00	0	~~2~~ 1	~~2~~ 1	~~8~~ 7	0	0	9	~~132.0~~ 135.0		0	0.0	0.0	0.0	0.0			
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB			
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	237.8	0.0	8	9	9	52	0	0	53	795.0		0	0.0						

PROJECT NAME: **HARTLAND-BETHEL**
PROJECT NUMBER: **STPG SIGN (40)**

FILE NAME: **BETHEL VT ROUTE 12 SB**
PROJECT MANAGER: **AMY GAMBLE**
DESIGNED BY: **M. MILLER**
BETHEL VT-12 SOUTHBOUND 6

PLOT DATE: **8/1/2012**
DRAWN BY: **M. MILLER**
CHECKED: **AMY GAMBLE**
SHEET **82** OF **85**