TOWN TOTAL SIGN SUMMARY SHEET

Hartland - Bethel STPG SIGN(40)

Town - Route	County	Town Mileage	NEW SIGNS (SF)		EXISTING SIGNS (EA)				EXIST POST (EA)		NUMBER OF NEW POSTS (EA)				SQUARE STEEL (FT)			TUBULAR STEEL Ø (IN)				
											1.75"	2"	2.5"		1.75"	2.00"	2.50"		3.00	3.50	4.00	5.00
											(LB / FT)				(LB / FT)				(LB / FT)			
			TYPE A	TYPE B	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE	1.88	2.42	3.35	TOTAL POSTS	1.88	2.42	3.35	FOUNDATION	7.60	9.00	10.80	14.60
Hartland VT-12 NB	Windsor	7.705	339.4	0	18	1	1	68	0	0	0	54	4	58	0	810	60					
Hartland VT-12 SB	Windsor	7.705	277.6	0	12	3	3	64	0	0	0	47	2	49	0	705	30					
Woodstock VT-12 NB	Windsor	3.298	126.3	0	12	6	6	32	0	0	0	24	0	24	0	360	0					
Woodstock VT-12 SB	Windsor	3.298	141.5	0	7	1	1	25	0	0	0	26	0	26	0	390	0					
Pomfret VT-12 NB	Windsor	1.383	12.5	0	0	0	0	2	0	0	0	2	0	2	0	30	0					
Pomfret VT-12 SB	Windsor	1.383	32.1	0	1	0	0	8	0	0	0	6	0	6	0	90	0					
Barnard VT-12 NB	Windsor	9.615	322.2	0	6	2	2	59	0	0	0	65	0	65	0	975	0					
Barnard VT-12 SB	Windsor	9.615	441.5	0	2	3	3	78	0	0	0	87	0	87	0	1305	0					
Bethel VT-12 NB	Windsor	6.057	210.3	0	27	1	1	38	0	0	0	45	0	45	0	675	0					
Bethel VT-12 SB	Windsor	6.057	237.8	0	8	9	9	52	0	0	1	52	0	52	15	780	0					
				Sub-Total		26	26	426					**Sub-Total**		15	6120	90					
Estimated Salvaged Street Name Signs to be erected onto new posts (Sheet 2, General Note 4):							0	0														
Salvaged Mile Marker Signs to be erected onto new posts (Sheet 2, General Notes 2, 3 & 4):							25	32														
		TOTAL =	2141.2	0	93	26	51	458	0	0	1	408	6	414	6225			0	0	0	0	0

PROJECT NAME: HARTLAND - BETHEL

PROJECT NUMBER: STPG SIGN (40)

FILE NAME: I2C116.SS
PROJECT LEADER: A. GAMBLE
DESIGNED BY: M. MILLER
TOWN TOTAL SIGN SUMMARY SHEET

PLOT DATE: 01-AUG-2012
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE
SHEET 85 OF 85