DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SEARSBURG VT-8 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	2.695	E	R1-1	36	36			9.00								2		13'-5" 13'-11" X								ANCHORS IN LEDGE INSTALL DIRECTLY ACROSS FROM EXISTING STOP SIGN.	X		
SB	2.685	F	M3-3	24	12			2.00								2		14'-2" 14'-4" X							#1A	INSTALL 10 FEET NORTH OF UTILITY POLE.		5	E-136B
		F	M1-5	24	24			4.00																				E-136B
		F	M4-5	24	12			2.00																				E-136B
		F	M1-5	30	24			5.00																				E-136B
SB	2.670	F	VR-041	24	24		THROUGH WAY BEGINS HERE						1		X													
		E	VR-040	24	24		THROUGH WAY ENDS HERE						1															
SB	2.635	F	M3-3	24	12		SOUTH						1		X													
		F	M1-5	24	24		VERMONT 8						1															
		F	M4-5	24	12		TO						1															
		F	M1-5	30	24		VERMONT 100						1															
		F	VD2-1	72	12			6.00								2		13'-3" 13'-6" X									8	
		F	VD2-1	72	12			6.00																			8	
		F	VD-700	6	10		MILEMARKER 0080 0212 0260						1															
SB	2.595	F	D2-1	72	10		HEARTWELLVILLE 6						1		X													
		F	D2-1	72	10		STAMFORD 12						1															
							SHEET TOTALS	34.00	0.00	0	0	0	~~9~~ 8	0	0	6		90.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	121.5	0.0	0	0	0	~~29~~ 30	0	0	19		285.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(41)

FILE NAME: 12C118
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
SEARSBURG SB SHEET 1

PLOT DATE: 2/13/2013
DRAWN BY: J. KELLY
CHECKED A. GAMBLE
SHEET 25 OF 97