DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SEARSBURG VT-8 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	S3-1	36	36	FYG		9.00								2		14'-2" 15'-2" X								ANCHORS IN LEDGE	X		
SB	1.763	F	W1-2MR	30	30		MODIFIED RIGHT CURVE						1		X											REMOVE ENTIRE SIGN ASSEMBLY.			
SB	1.730	F	W1-10R	36	36			9.00								2		17'-7" 16'-7" X								INSTALL 175 FEET SOUTH OF EXISTING RIGHT CURVE SIGN ASSEMBLY.	X		
SB	1.315	F	W1-2R	30	30		RIGHT CURVE						1		X														
		F	W13-1	18	18		35 MPH ADVISORY						1																
SB	1.253	F	W1-2R	30	30			6.25								1		13'-0" X								INSTALL 325 FEET SOUTH OF EXISTING RIGHT CURVE SIGN ASSEMBLY.	X		
		F	W13-1P	18	18			2.25																			X		
SB	1.070	F	VW-054L	30	30		HIDDEN DRIVE LEFT						1		X														
SB	1.005	F	W1-2L	30	30		LEFT CURVE						~~1~~		X											SIGN ASSEMBLY NOT FOUND IN THE FIELD			
		F	W13-1	18	18		40 MPH ADVISORY						~~1~~																
SB	0.338	F	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
		F	W13-1	18	18		35 MPH ADVISORY						1																
SB	0.300	F	W2-2L	30	30		SIDE ROAD LEFT						1		X														
		F	W13-1	18	18		35 MPH ADVISORY						1																
SB	0.270	F	VW-133L	30	30			6.25								1		14'-10" X								INSTALL 160 FEET SOUTH OF EXISTING SIDE ROAD LEFT ASSEMBLY.		7	
							SHEET TOTALS	32.75	0.00	0	0	0	~~10~~ 8	0	0	6	90.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	121.5	0.0	0	0	0	~~30~~ 29	0	0	19	285.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
SEARSBURG SB SHEET 3

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **27** OF **97**