DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
JAMAICA VT-30 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	VD-700	6	10		MILEMARKERS (2)						2																
NB	0.000	C	VD-024	60	7.5								1		X														
		C	VD-024	72	10		Jamaica / Townshend	5.00								2		12'-6" 13'-1" X									4, 8	
		C	VD-700	6	10		0300 1309 0000	0.42																		INSTALL BELOW JAMAICA ON LH POST.		E-138
		C	VD-700	6	10		0300 1317 0736	0.42																		INSTALL BELOW TOWNSHEND ON RH POST.		E-138
NB	0.175	A	VW-202	30	30								1	X															
		A	VW-202	30	30		TRUCKS ENTERING	6.25																		INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.		7	
NB	0.600	A	M2-1	21	15		JCT			1				X															
		A	M1-5	30	24		VERMONT ROUTE 100			1																			
NB	0.622	A	D1-1A	72	10		DESTINATION SIGN ASSEMBLY			1				X															
		A	D1-1S	72	10					1																			
		A	D1-1A	72	10					1																			
		A	D1-1A	72	10					1																			
NB	0.662	A	M3-3	24	12		ROUTE MARKER ASSEMBLY			1				X															
		A	M1-5	30	24					1																			
		A	M6-1	21	15					1																			
SIGN SUMMARY SHEET							SHEET TOTALS	12.09	0.00	9	0	0	4 ~~2~~	0	0	2		30.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	~~438.5~~ ~~443.5~~	0.0	32 ~~29~~	2 ~~1~~	2 ~~1~~	88 ~~78~~	0	0	63 ~~62~~		945.0 ~~930.0~~		0	0.0							

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
JAMAICA NB SHEET 1

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **29** OF **97**