| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION SHSM | SIGN DETAIL LOCATION PROJECT SHEET # | SIGN DETAIL LOCATION STANDARD SHEET # |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **JAMAICA VT-30 NB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| | | A | M3-1 | 24 | 12 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | M1-5 | 24 | 24 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | M6-3 | 21 | 15 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | M3-1 | 24 | 12 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | M1-5 | 30 | 24 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | M6-3 | 21 | 15 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| NB | 0.675 | C | W1-7 | 48 | 24 | | DOUBLE ARROW | | | 1 | | | | X | | | | | | | | | | | | | | | |
| NB | 0.700 | A | M3-1 | 24 | 12 | | ROUTE MARKER ASSEMBLY | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | A | M1-5 | 24 | 24 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | M3-1 | 24 | 12 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| | | A | M1-5 | 30 | 24 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| NB | 0.740 | A | D2-1 | 72 | 10 | | DESTINATION SIGN ASSEMBLY | | | 1 | | | | X | | | | | | | | | | | | | | | |
| | | A | D1-1S | 72 | 10 | | | | | 1 | | | | | | | | | | | | | | | | | | | |
| NB | 0.773 | A | R2-1 | 24 | 30 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | A | R2-1 | 24 | 30 | | SPEED LIMIT 50 | ~~6.25~~ 5.00 | | | | | | | | | | | | | | | | | | | INSTALL ON EXISTING FLANGED CHANNEL SIGN POST. | X | | |
| | | | | | | | SHEET TOTALS | ~~6.25~~ 5.00 SF | 0.00 SF | 13 EA | 0 EA | 0 EA | 1 EA | 0 EA | 0 EA | 0 EA | | 0.0 FT | | 0 EA | 0.0 LB | 0.0 LB | 0.0 LB | 0.0 LB | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | ~~438.5~~ ~~443.5~~ | 0.0 | ~~32~~ ~~29~~ | ~~2~~ ~~1~~ | ~~2~~ ~~1~~ | ~~88~~ ~~78~~ | 0 | 0 | ~~63~~ ~~62~~ | | ~~945.0~~ ~~930.0~~ | | 0 | 0.0 | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
JAMAICA NB SHEET 2

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**