DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
JAMAICA VT-30 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	VR-017	24	30								1	~~X~~	X											MEADOWS RD (TH-64)			
		C	VR-017	24	30			5.00								1		13'-7" X								INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.		6	
		A	D3-1	58	12			4.83								2		13'-0" 14'-6" X								FIELD LOCATE AS TO NOT BLOCK OTHER SIGNAGE.		11	
NB	3.370	D	R1-1	30	30								1	X												MEADOWS RD (TH-64)			
		D	R1-1	30	30			6.25																				X		
NB	3.480	A	W3-5	36	36								1		X														
		A	W3-5	36	36			9.00								2		13'-11" 13'-9" X										X	
NB	3.532	A	VD-018	30	18			3.75								1		12'-0" X								INSTALL 275 FEET NORTH OF SPEED REDUCTION (30) SIGN ASSEMBLY.		5	
NB	~~3.590~~ 3.592	A	R2-1	24	30								1		X														
		A	R2-1	30	36			7.50								1		X								INSTALLED AS EXISTING USED EXISTING ANCHOR ~~INSTALL ON LEFT AS EXISTING.~~	X		
NB	~~3.590~~ 3.594	A	R7-2S	24	36		NO PARKING 12AM TO 6 AM, NOV 1 -APR 1						1		X														
		A	VR-644P	24	12								1																
		A	R3-9cP	30	12			2.50								1		X								~~INSTALL ON RIGHT SIDE OF SPEED LIMIT 30 SIGN.~~	X		
		A	R8-3	24	24			4.00																		INSTALLED AS EXISTING USED EXISTING ANCHOR	X		
		A	VR-122	24	12			2.00																				6	
SIGN SUMMARY SHEET							SHEET TOTALS	44.83	0.00	0	0	0	6	0	0	~~8~~ 7		~~120.0~~ 105.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	~~438.5~~ 443.5	0.0	~~32~~ 29	~~2~~ 1	~~2~~ 1	~~88~~ 78	0	0	~~63~~ 62		~~945.0~~ 930.0		0	0.0								

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
JAMAICA NB SHEET 5

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **33** OF **97**