DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
JAMAICA VT-30 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	4.440	A	R2-1	24	30								1		X													
		A	R2-1	24	30			5.00								1		15'-7" X								X		
NB	5.748	B	W7-1B	48	48		HILL SYMBOL - 8%						1		X													
		B	W7-3A	24	18		NEXT 2 MILES						1															
NB	6.323	A	W2-2ML	30	30		LEFT SIDE ROAD						1		X													
		A	VW2-7L Mo	30	30			6.25								1		15'-10" X									7	
NB	6.515	C	VR-017	24	24								1		X											STRATTON GATE RD (TH-93)		
		C	VR-017	24	30			5.00								1		14'-9" X									6	
NB	6.521	C A	VD-700 D3-1	6 UNK	10 UNK								1													STRATTON GATE RD (TH-93)		
		C D	VD-700 R1-1	6 30	10 30								1 1		X													
		D	R1-1	30	30			0.42 6.25								1		14'-2" X								X		
		A	D3-1	72	12			6.00								2		14'-0" 14'-0" X								FIELD LOCATE AT LEAST 8 FEET FROM STOP SIGN AS TO NOT BLOCK OTHER SIGNS.		11
NB	6.581	A	S3-1T	30	30		SCHOOL BUS STOP AHEAD						1		X															
		A	S3-1	36	36	FYG		9.00								2		14'-4" 14'-9" X									X	
NB	6.957	C	VR-017	24	30								1	X												STONE HEDGES RD (TH-94)		
SIGN SUMMARY SHEET							SHEET TOTALS	~~37.92~~ ~~37.50~~ SF	0.00 SF	0 EA	0 EA	0 EA	~~10~~ ~~9~~ EA	0 EA	0 EA	8 EA	120.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	~~438.5~~ ~~443.5~~	0.0	~~32~~ ~~29~~	~~2~~ ~~1~~	~~2~~ ~~1~~	~~88~~ ~~78~~	0	0	~~63~~ ~~62~~	~~945.0~~ ~~930.0~~		0	0.0								

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118** PLOT DATE: **2/13/2013**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED **A. GAMBLE**
JAMAICA NB SHEET 8 SHEET **36** OF **97**