DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
JAMAICA VT-30 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	4.500	F	W7-1B	36	36		HILL SYMBOL						1		X														
SB	4.480	F	VD-018	30	18			3.75								1		15'-0" X								INSTALL 100 FEET NORTH OF EXISTING VILLAGE SIGN ASSEMLY.		5	
SB	4.460	F	VD-018	30	18		JAMAICA EAST JAMAICA 3						1		X														
SB	4.440	F	R2-1	24	30								1		X														
		F	R2-1	30	36			7.50								1		15'-0" X								INSTALL DIRECTLY ACROSS FROM NB SPEED LIMIT 50 SIGN ASSEMBLY.	X		
SB	4.390	F	W1-2L	30	30		LEFT CURVE						1		X														
		F	W13-1	18	18		35 MPH ADVISORY						1																
SB	4.340	F	W1-2L	30	30			6.25								1		14'-11" X								INSTALL 200 FEET NORTH OF SPEED REDUCTION (30) SIGN ASSEMBLY.	X		
		F	W13-1P	18	18			2.25																			X		
SB	4.300	F	W3-5	36	36								1		X														
		F	W3-5	36	36			9.00								2		14'-6" 14'-4" X									X		
SB	4.255	F	VD-062B	72	16		BUSINESS SIGN			1				X															
		F	VD-062BRN	72	16		BUSINESS SIGN			1																			
SB	4.220	F	VW-054L	30	30								1		X														
		F	VW-054L	30	30			6.25								1		14'-2" X										7	
							SHEET TOTALS	35.00	0.00	2	0	0	7	0	0	6		90.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	431.84 ~~430.2~~	0.0	31 ~~29~~	2 ~~0~~	2 ~~0~~	85 ~~82~~	0	0	66 ~~63~~		990.0 ~~945.0~~		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTWEST REGION
PROJECT NUMBER: STPG SIGN(41)

FILE NAME: 12C118
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
JAMAICA SB SHEET 9

PLOT DATE: 2/13/2013
DRAWN BY: J. KELLY
CHECKED A. GAMBLE