DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
JAMAICA VT-30 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	4.180	F	R2-1	30	36								1		X														
		F	R2-1	30	36			7.50								1		13'-1" X								INSTALL NEW SIGN DIRECTLY ACROSS FROM THE NB SPEED LIMIT 40 SIGN.	X		
SB	4.132	F	W11-8	36	36								1		X														
		F	W11-8	30	30			6.25								1		14'-3" X									X		
			SKIP TO SOUTH SIDE OF BRIDGE #30																										
SB	3.903	F	R8-3	24	24			4.00								1		12'-10" X								INSTALL AT END OF STONE WALL.	X		
		F	VR-122	24	12			2.00																				6	
SB	3.878	F	W11-2	30	30		PEDESTRIAN ADVANCE WARNING SIGN			1				X															
		F	W16-7	24	12		DOWNWARD ARROW			1																			
SB	3.851 ~~3.858~~	G	VR-017	24	24								1	~~X~~												PIKES FALLS RD (TH-1)			
SB	3.858	G G	R2-1 VR-017	24 24	30 30			5.00			1 ~~1~~	1 ~~1~~				1		14'-4" X								INSTALLED ON POST WITH VILLAGE SPEED LIMIT 25 SIGN ~~INSTALL ON EXISTING SIGN POST.~~		6	
SB	3.858	H	R1-1	30	30		STOP						~~1~~													NOT FOUND IN FIELD			
SB	3.851	G H	VD-700 R1-1	6 30	10 30								1 1	X												PIKES FALLS RD (TH-1)			
		G H	VD-700 R1-1	6 30	10 30			0.42 6.25																		INSTALL ON EXISTING SIGN POST.	X		
SB	3.851	F	D3-1	60	12			5.00								~~2~~		~~X~~								~~FIELD LOCATE SIGN ASSEMBLY AS TO NOT BLOCK OTHER SIGNS.~~		11	
							SHEET TOTALS	36.42 ~~36.00~~	0.00	2	1 ~~0~~	1 ~~0~~	5	0	0	4 ~~5~~		60.0 ~~75.0~~		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	431.84 ~~430.2~~	0.0	31 ~~29~~	2 ~~0~~	2 ~~0~~	85 ~~82~~	0	0	66 ~~63~~		990.0 ~~945.0~~		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTWEST REGION
PROJECT NUMBER: STPG SIGN(41)

FILE NAME: 12C118
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
JAMAICA SB SHEET 10

PLOT DATE: 2/13/2013
DRAWN BY: J. KELLY
CHECKED: A. GAMBLE