DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
JAMAICA VT-30 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	3.815	F	R2-1	24	30								1	X														
		F	R7-2S	24	36		NO PARKING (DATES)						1															
		F	R2-1	24	30			5.00																	INSTALL NEW SIGNS ON EXISTING FLANGED CHANNEL SIGN POST.	X		
		F	R8-3	24	24			4.00																			X		
		F	VR-122	24	12			2.00																				6	
SB	3.755	F	R2-1	24	30			5.00								1	12'-8" X									INSTALL NORTH OF UTILITY POLE WITH CONDUIT, ACROSS FROM THREE MOUNTAIN INN.	X		
SB	3.590	F	R2-1	24	30								1		X													
		F	R2-1	24	30			5.00								1	13'-11" X									INSTALL DIRECTLY ACROSS FROM NB SPEED LIMIT 30 SIGN ASSEMBLY.	X		
SB	3.590	F	R7-2S	24	36		NO PARKING (DATES)						1		X													
		F	M4-6	24	12		END						1															
		F	R3-9dP	30	12			2.50								1	11'-11" X									INSTALL TO THE RIGHT OF SPEED LIMIT 40 ASSEMBLY.	X		
		F	R8-3	24	24			4.00																			X		
		F	VR-122	24	12			2.00																				6	
SB	3.310	F	R2-1	24	30								1		X													
		F	R2-1	24	30			5.00								1	13'-6" X										X		
							SHEET TOTALS	34.50 SF	0.00 SF	0 EA	0 EA	0 EA	6 EA	0 EA	0 EA	4 EA	60.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	~~431.84~~ ~~430.2~~	0.0	~~31~~ ~~29~~	~~2~~ ~~0~~	~~2~~ ~~0~~	~~85~~ ~~82~~	0	0	~~66~~ ~~63~~	~~990.0~~ ~~945.0~~		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
JAMAICA SB SHEET 11

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**