DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
JAMAICA VT-30 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	1.952	G	VR-017	24	24								1	X												RIVER RD (TH-41)			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																		INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.		6	
		G	UNK	18	24		CHILDREN AT PLAY						1													REMOVE NON-COMPLIANT SIGN.			
SB	1.945	G H	VD-700 R1-1	6 30	10 30		0300 1309 0195						1	X												RIVER RD (TH-41)			
		H	R1-1	30	30		STOP	6.25																		INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.	X		
SB	1.945	F	D3-1	UNK	UNK								1		X											RIVER RD (TH-41)			
		F	D3-1	44	12		River Rd J41	3.67								2		11'-0" 11'-6" X								ANCHORS IN LEDGE		11	
SB	1.856	F	VW-619	30	30		SHOULDER NARROWS						1		X														
SB	1.704	F	VW-619	36	36		SHOULDER NARROWS	9.00								2		12'-10" 13'-8" X								INSTALL 800 FEET SOUTH OF EXISTING SHOULDER NARROWS SIGN ASSEMBLY.		7	
SB	0.834	F	M2-1	21	15		JCT			1				X															
		F	M1-5	30	24		VERMONT ROUTE 100			1																			
SB	0.789	F	D1-1A	72	10		DESTINATION SIGN ASSEMBLY			1				X															
		F	D1-1A	72	10					1																			
		F	D1-1A	72	10					1																			
		F	D1-1A	72	10					1																			
SIGN SUMMARY SHEET							SHEET TOTALS	23.92	0.00	~~7~~ 6	0	0	5	0	0	4		60.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	431.84 ~~430.2~~	0.0	31 ~~29~~	2 ~~0~~	2 ~~0~~	85 ~~82~~	0	0	66 ~~63~~		990.0 ~~945.0~~		0	0.0							

PROJECT NAME: **STATEWIDE SOUTWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
JAMAICA SB SHEET 12

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**