DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WELLS VT-31 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.000	B	VR-040	24	24		THROUGH WAY ENDS HERE						1		X													
		A	VR-041	24	24		THROUGH WAY BEGINS HERE						1															
		A	R2-1	24	30								1															
		A	VR-039	24	18			3.00								1		15'-0" X									6	
		A	R2-1	24	30		STATE HIGHWAY BEGINS / STATE HIGHWAY ENDS	5.00																		X		
		B	VR-038	24	18		SPEED LIMIT 45	3.00																			6	
NB	0.025	A	VD-421	60	48		Welcome To VERMONT	20.00								2			10'-7" 10'-7" X							INSTALL AT NORTH END OF PULL-OFF, NORTH OF TRAFFIC COUNTER..		5	
NB	0.061	A	M3-1	24	12								1		X													
		A	M1-5	24	24								1															
		A	M3-1	24	12		NORTH	2.00								1		14'-0" X										E-136B
		A	M1-5	24	24		VERMONT 31	4.00																				E-136B
NB	0.095	A	VR-048	24	30		STATE LAW STOP FOR SCHOOL BUS						1		X													
		A	VR-654	24	24			4.00								1		14'-0" X									6	
NB	0.187	A	VR-601A	24	30		BUCKLE UP IT'S THE LAW — SAFETY BELTS REQUIRED						1	X														
		A	VR-601	36	36			9.00																		INSTALL NEW ON EXISTING FLANGED CHANNEL POST BEHIND RAIL.		6	
SIGN SUMMARY SHEET							SHEET TOTALS	50.00	0.00	0	0	0	7	0	0	5		75.0		0	0.0	0.0	0.0	0.0	PROJECT NAME: STATEWIDE SOUTHWEST REGION PROJECT NUMBER: STPG SIGN(41)			
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	136.7	0.0	0	0	0	~~30~~ 31	0	0	19		285.0		0	0.0				FILE NAME: 12C118 PROJECT MANAGER: A. GAMBLE DESIGNED BY: J. KELLY WELLS NB SHEET 1	PLOT DATE: 2/13/2013 DRAWN BY: J. KELLY CHECKED A. GAMBLE SHEET 57 OF 97		