DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WELLS VT-31 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.266	A	VR-654	24	24		NO DWI						1		X														
		A	VR-655	24	18		STRICTLY ENFORCED						1																
NB	0.342	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
		A	W13-1	18	18		35 MPH ADVISORY						1																
NB	0.400	A	VW-060	30	30								1	X																
		A	VW-060	30	30			6.25																			INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.		7	
NB	0.438	A	W1-4R	30	30			6.25								1		16'-0" X									INSTALL 200 FEET NORTH OF HIDDEN DRIVES SIGN ASSEMBLY.	X		
		A	W13-1P	18	18			2.25																				X		
NB	0.593	A	R2-1	24	30								1		X														
		A	R2-1	24	30			5.00								1		14'-0" X										X		
NB	0.800	C A	VD-700 W1-4R	6 30	10 30		RIGHT REVERSE CURVE						1 1		X														
NB	1.085	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
		A	W13-1	18	18		35 MPH ADVISORY						1																
NB	1.135	A	W1-4R	30	30			6.25								1		15'-0" X									INSTALL 260 FEET NORTH OF EXISTING ASSEMBLY.	X		
NB	1.270	D	R1-1	30	30								~~1~~		~~X~~												HILL TOP RD (TH-11) SOUTHERLY LEG.	SIGN ASSEMBLY NOT FOUND IN THE FIELD		
							SHEET TOTALS	26.00	0.00	0	0	0	10	0	0	3		45.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	136.7	0.0	0	0	0	31 ~~30~~	0	0	19		285.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WELLS NB SHEET 2

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**