DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WELLS VT-31 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	1.738	F	W1-8L	18	24								1		X														
		E	W1-8R	18	24								1																
		F	W1-8L	18	24	FY		3.00								1		14'-3" X								INSTALL SIGNS BACK TO BACK ON SAME SIGN POST.	X		
		E	W1-8R	18	24	FY		3.00																			X		
SB	1.710	F	W1-8	18	24								1		X												SIGN ASSEMBLY NOT FOUND IN THE FIELD			
		E	W1-8	18	24								1																
		F	W1-8L	18	24	FY		3.00								1		14'-5" X								INSTALL SIGNS BACK TO BACK ON SAME SIGN POST.	X		
		E	W1-8R	18	24	FY		3.00																			X		
SB	1.680	F	W1-2R	30	30		RIGHT CURVE						1		X														
		F	W13-1	18	18		35 MPH ADVISORY						1																
SB	1.660	F	W1-2R	30	30	FY		6.25								1		15'-2" X								INSTALL 100 FEET SOUTH OF EXISTING RIGHT CURVE SIGN ASSEMBLY.	X		
		F	W13-1P	18	18	FY		2.25																			X		
SB	1.630	F	S3-1T	30	30		SCHOOL BUS STOP AHEAD						1		X															
		F	S3-1	36	36	FYG		9.00								2		14'-6" 14'-2" X									X		
SB	1.465	F	R2-1	24	30								1		X														
							SHEET TOTALS	29.50 SF	0.00 SF	0 EA	0 EA	0 EA	~~6~~ 8 EA	0 EA	0 EA	5 EA		75.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB				
							TOWN DIRECTIONAL TOTALS	75.8	0.0	1	0	0	~~15~~ 18	0	0	11		165.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WELLS SB SHEET 1

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **61** OF **97**