DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WELLS VT-31 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	R2-1	24	30			5.00								1		12'-5" X									X		
SB	1.360	F	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
		F	W13-1	18	18		35 MPH ADVISORY						1																
SB	1.300	F	W1-4R	30	30			6.25								1		14'-2" X								INSTALL 325 FEET SOUTH OF EXISTING REVERSE CURVE ASSEMBLY.	X		
SB	1.070	F	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
SB	0.765	F	W11-5	30	30		FARM MACHINERY						~~1~~		~~X~~											SIGN ASSEMBLY NOT FOUND IN THE FIELD			
		F	R2-1	24	30			5.00								1		14'-7" X									X		
SB	0.710	F	R2-1	24	30		SPEED LIMIT 45						1		X														
SB	0.670	F	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
		F	W13-1	18	18		35 MPH ADVISORY						1																
SB	0.625	F	VW-060	30	30								1	~~X~~	X														
		F	VW-060	30	30			6.25								1		11'-0" X								~~INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.~~		7	
SB	0.587	F	W1-4R	30	30			6.25								1		15'-0" X								INSTALL 200 FEET SOUTH OF HIDDEN DRIVES SIGN ASSEMBLY.	X		
		F	W13-1P	18	18			2.25																			X		
SB		F	S3-1T	30	30		NEW YORK INSTALLED SCHOOL BUS STOP AHEAD			1				X												EXACT MILE POINT UNKNOWN. RETAIN ASSEMBLY.			
							SHEET TOTALS	31.00	0.00	1	0	0	~~7~~ 8	0	0	4		60.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	75.8	0.0	1	0	0	~~15~~ 18	0	0	11		165.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WELLS SB SHEET 2

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **62** OF **97**