DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POULTNEY VT-31 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	VD-700	6	10		MILE MARKERS (2)						2																
NB	0.000	C	VD-024	60	7.5								1		X														
		C	VD-024	72	10		Poultney | Wells	5.00								2		10'-0" 10'-0" X								ANCHORS IN LEDGE		8	
		C	VD-700	6	10		0310 1117 0000	0.42																		INSTALL ON LEFT POST BELOW POULTNEY.			E-138
		C	VD-700	6	10		0310 1126 0176	0.42																		INSTALL ON RIGHT POST BELOW WELLS.			E-138
NB	0.270	A	R2-1	24	30								1		X														
		A	R2-1	24	30		SPEED LIMIT 45	5.00								1		14'-0" X									X		
NB	0.340	A	UNK				UNKNOWN MISSING SIGN						~~1~~		~~X~~											EMPTY POST NOT FOUND IN FIELD ~~REMOVE EMPTY SIGN POST.~~			
NB	0.570	A	W11-5	30	30								1	X															
		A	W11-5	30	30			6.25																		INSTALL NEW SIGN ON EXISTING FLANGED CHANNEL SIGN POST.	X		
NB	0.710	A	R2-1	24	30								1		X														
		A	R2-1	24	30		SPEED LIMIT 45	5.00								1		15'-6" X									X		
		A	W8-9	30	30		LOW SHOULDERS						1													REMOVE THIS NON-COMPLIANT SIGN.			
NB	0.768	A	S3-1T	30	30		SCHOOL BUS STOP AHEAD						1	X															
		A	VW-054L	30	30		HIDDEN DRIVE LEFT						1																
		A	S3-1	36	36	FYG		9.00																		INSTALL NEW SIGN ON EXISTING FLANGED CHANNEL SIGN POSTS. TRIM IF NECESSARY.	X		
							SHEET TOTALS	31.09	0.00	0	0	0	~~8~~ 9	0	0	4		60.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	~~243.2~~ 248.2	0.0	2	0	0	~~57~~ 60	0	0	~~25~~ 27		~~375.0~~ 405.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(41)

FILE NAME: 12C118
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
CHECKED: A. GAMBLE
PLOT DATE: 2/13/2013
DRAWN BY: J. KELLY

POULTNEY NB SHEET 1