DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POULTNEY VT-31 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		C	R2-1	24	30			5.00										14'-9"								INSTALL SPEED LIMIT 25 BELOW LEGAL LOAD LIMIT			
		C	VR-017	24	30			5.00								1		X										6	
NB	2.510	D	R1-1	30	30								1		X												JONES RD (TH-35)			
		D	R1-1	30	30			6.25								1		8'-3" X								INSTALL ON EAST SIDE OF TREE.	X		
NB	2.510	A	D3-1	UNK	UNK								1		X												JONES RD (TH-35)			
		A	D3-1	34	12			2.83								1		11'-6" X								INSTALL ON WEST SIDE OF TREE.		12	
NB	2.700	A	W1-4R	30	30		RIGHT REVERSE CURVE						1	X																
		A	W13-1	18	18		35 MPH ADVISORY						1																	
		A	R2-1	24	30			5.00																		INSTALL NEW SIGN ON EXISTING FLANGED CHANNEL SIGN POST.	X		
NB	~~2.850~~ 2.812	A	W1-4R	30	30			6.25								1		15'-0" X								INSTALL SIGN ASSEMBLY 800 FEET NORTH OF EXISTING RIGHT REVERSE CURVE ASSEMBLY.	X		
		A	W13-1P	18	18			2.25																			X		
NB	3.117	A	R2-5A	24	30		REDUCED SPEED AHEAD						1		X															
NB	3.160	A	VD-062C	74.75	16		BUSINESS SIGN			1				X																
		A	VD-062BC	74.75	16		BUSINESS SIGN			1																				
NB	3.202	B	VR-039	24	18		STATE HIGHWAY BEGINS						1	X																
		A	VR-040	24	24		THROUGH WAY ENDS HERE						1																	

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN)	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00	TUBULAR STEEL Ø (IN) 3.50	TUBULAR STEEL Ø (IN) 4.00	TUBULAR STEEL Ø (IN) 5.00
SHEET TOTALS	~~32.58~~ ~~27.58~~	0.00	2	0	0	7	0	0	4	60.0	0	0.0	0.0	0.0	0.0
	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	EA	LB	LB	LB	LB
TOWN DIRECTIONAL TOTALS	~~248.2~~ ~~243.2~~	0.0	2	0	0	~~60~~ ~~57~~	0	0	~~27~~ ~~25~~	~~405.0~~ ~~375.0~~	0	0.0			

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
POULTNEY NB SHEET 5

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **68** OF **97**