DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POULTNEY VT-31 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	2.480	F	R2-1	24	30		SPEED LIMIT 50						1		X													
SB	2.473	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		14'-0" X								INSTALL NEW SIGN 10 FEET NORTH OF UTILITY POLE AND DIRECTLY ACROSS FROM NB SPEED LIMIT 40.			
SB	2.275	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X													
		F	S3-1	36	36	FYG		9.00								2		15'-6" 15'-7" X									X	
SB	2.240	F	W2-2L	30	30		SIDE ROAD LEFT						1	X														
		F	S3-1T	30	30		SCHOOL BUS STOP AHEAD						1															
		F	W2-2L	30	30			6.25																		INSTALL NEW SIGNS ON EXISTING FLANGED CHANNEL SIGN POSTS.	X		
		F	VW-054R	30	30			6.25																				7
SB	2.200	F	VD-062B	72	16		BUSINESS SIGN			1				X														
		F	VD-062B	72	16		BUSINESS SIGN			1																		
SB	2.000	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X													
SB	1.976	F	VW-054R	30	30			6.25								1		13'-0" X								INSTALL 125 FEET SOUTH OF EXISTING HIDDEN DRIVE RIGHT SIGN ASSEMBLY.		7	
SB	1.225	F	R2-1	30	36			7.50								1		16'-9" X								INSTALL DIRECTLY ACROSS FROM NEW NB SPEED LIMIT 50 SIGN ASSEMBLY.	X		
SB	1.205	F	W1-2L	30	30		LEFT CURVE						1		X													
		F	W13-1	18	18		35 MPH ADVISORY						1															
SIGN SUMMARY SHEET							SHEET TOTALS	40.25	0.00	2	0	0	7	0	0	5		75.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	207.2	0.0	2	0	0	~~41~~ 43	0	0	~~29~~ 31		~~435.0~~ 465.0		0	0.0							

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118** PLOT DATE: **2/13/2013**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED **A. GAMBLE**
POULTNEY SB SHEET 3 SHEET **74** OF **97**