DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POWNAL VT-346 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		A	VD-700	6	10		MILE MARKER 3460 0208 0000				1																	
		A	W1-4R	30	30		RIGHT REVERSE CURVE						1															
		A	VD-700	6	10		MILE MARKER					1						15'-0"									
		A	W11-8	30	30			6.25								1		X								X		
NB	0.157	A	R8-3A	24	24		NO PARKING			1				X														
NB	0.185	A	VD-018	30	18		VILLAGE SIGN			1				X														
NB	0.205	A	R8-3A	24	24		NO PARKING			1				X														
NB	0.273	C	VR-017	24	30		LEGAL LOAD 24K			1				X														
NB	0.273	D	R1-1	30	30		STOP			1				X														
		A	D3-1	UNK	UNK		Oak Hill School Rd						1		X			13'-0"									
NB	0.275	A	D3-1	70	12			5.83								2		13'-0" X								FIELD LOCATE AS TO NOT BLOCK OTHER SIGNAGE.		12
NB	0.295	A	R2-1	24	30		SPEED LIMIT 35			1				X														
		A	R8-3A	24	24		NO PARKING			1																		
NB	0.400	A	W1-2L	30	30		LEFT CURVE			1				X														
NB	0.464	A	W1-1R	30	30		RIGHT TURN			1				X														
		A	W13-1	18	18		20 MPH ADVISORY			1																		
NB	0.503	A	M3-1	24	12		NORTH			1				X														
		A	M1-5	30	24		VERMONT ROUTE 346			1																		
							SHEET TOTALS	12.08	0.00	12	~~1~~ 0	~~1~~ 0	~~2~~ 1	0	0	3		45.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	224.3	0.0	~~31~~ 28	~~3~~ 0	~~3~~ 0	~~47~~ 44	0	0	~~32~~ 31		~~480.0~~ 465.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(41)

FILE NAME: 12C118
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
POWNAL NB SHEET 2

PLOT DATE: 2/15/2013
DRAWN BY: J. KELLY
CHECKED A. GAMBLE
SHEET 79 OF 97