DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POWNAL VT-346 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.575	A	R8-3A	24	24		NO PARKING			1				X															
NB	0.650	A	R2-1	24	30		SPEED LIMIT 50			1				X															
NB	0.723	A	VW-054L	30	30		HIDDEN DRIVE LEFT						1		X														
NB	0.823	A	R8-3A	24	24		NO PARKING			1				X															
		A	M4-6P	24	12		END			1																			
NB	0.884	A	UNK	UNK	UNK		EMPTY POST						1		X												REMOVE EMPTY POST.		
NB	1.112	A	W11-5	30	30			6.25								1	14'-11" X									INSTALL 875 FEET SOUTH OF EXISTING FARM MACHINERY SIGN ASSEMBLY.	X		
NB	1.285	A	W11-5	30	30		FARM MACHINERY						1		X														
NB	1.548	A	R2-1	24	30			5.00								1	14'-11" X									INSTALL ACROSS FROM RED GARAGE AT BEGINNING OF MARKED PASSING ZONE.	X		
NB	2.074	C	VR-017	24	30								~~1~~		~~X~~												CEDAR HILL RD (TH-27)			
		C	VR-017	24	30			5.00								1	14'-5" X											6	
NB	2.083	C D	VD-700 R1-1	6 30	10 30		MILE MARKER				1		1		X												CEDAR HILL RD (TH-27)			
		A	D3-1	UNK	UNK		CEDAR HILL RD STREET SIGN						1																
		C D	VD-700 R1-1	6 30	10 30		MILE MARKER	6.25				1				1	14'-5" X											X	
NB	2.083	A	D3-1	50	12			4.17								2	13'-0" 13'-0" X									FIELD LOCATE AT LEAST 8 FT FROM ANY OTHER SIGN.		12	
							SHEET TOTALS	26.67	0.00	4	~~1~~ 0	~~1~~ 0	~~5~~ 6	0	0	6	90.0			0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	224.3	0.0	~~31~~ 28	~~3~~ 0	~~3~~ 0	~~47~~ 44	0	0	~~32~~ 31	~~480.0~~ 465.0			0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
POWNAL NB SHEET 3

PLOT DATE: **2/15/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**