DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POWNAL VT-346 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.113	A	VW-444	30	30		WATCH FOR FALLEN ROCK						1		X													
		A	W1-4R	30	30		RIGHT REVERSE CURVE						1															
		A	W13-1	18	18		40 MPH ADVISORY						1															
NB	2.142	A	VW-285	30	30			6.25								1		14'-4" X								INSTALL NEW 150 FEET NORTH OF EXISTING FALLEN ROCK SIGN ASSEMBLY.		7	
NB	2.193	A	W1-4R	30	30			6.25								1		15'-0" X								INSTALL 425 FEET NORTH OF EXISTING REVERSE CURVE SIGN ASSEMBLY.	X		
		A	W13-1P	18	18			2.25																			X		
NB	2.465	A	W3-5	36	36		SPEED REDUCTION (35)			1				X														
NB	2.564	A	VD-018	30	18		NORTH POWNAL			1				X														
NB	2.610	A	R2-1	24	30		SPEED LIMIT 35			1				X														
NB	2.635	A	W1-4L	30	30		LEFT REVERSE CURVE			1				X														
NB	2.703	A	S3-1T	36	36		SCHOOL BUS STOP AHEAD			1				X														
NB	2.764	A	VW-133R	30	30		HIDDEN DRIVES RIGHT			1				X														
NB	2.798	A	R2-1	24	30		SPEED LIMIT 35			1				X														
NB	2.996	A	W11-8	30	30								1		X													
		A	W11-8	30	30			6.25								1		14'-9" X									X		
SIGN SUMMARY SHEET							SHEET TOTALS	21.00	0.00	7	0	0	4	0	0	~~3~~ 2		~~45.0~~ 30.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	224.3	0.0	~~31~~ 28	~~3~~ 0	~~3~~ 0	~~47~~ 44	0	0	~~32~~ 31		~~480.0~~ 465.0		0	0.0							

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118** PLOT DATE: **2/15/2013**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED **A. GAMBLE**
POWNAL NB SHEET 4 SHEET **81** OF **97**