DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POWNAL VT-346 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	3.036	A	R2-1	24	30								1	X														
		A	R2-1	24	30			5.00																	INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.	X		
NB	3.202	A	W-622	30	30								1		X													
		A	W-622	30	30			6.25								1		14'-6" X									7	
NB	3.344	A A	VD-700 R2-1	6 24	10 30		3460 0208 0330			1			1	X														
		A	R2-1	24	30			5.00																	INSTALL NEW SIGN ON EXISTING FLANGED CHANNEL SIGN POST.	X		
NB	3.472	A	W1-1L	30	30		LEFT TURN						1		X													
		A	W13-1	18	18		25 MPH ADVISORY						1															
NB	3.493	A	VD1-1	72	12			6.00								2		14'-0" 14'-0" X							INSTALL NEW SIGNS IN GRASS STRIP BETWEEN GREEN HOUSE AND CHURCH DRIVE.		10	
		A	VD1-1	72	12			6.00																			10	
NB	3.527	A A	VD-700 D1-1M	6 72	10 10		DESTINATION SIGNS 3460 0208 0350						1 1		X													
		A	D1-1M	72	10								1															
		A	W1-1L	30	30			6.25								1		15'-0" X							INSTALL SIGNS 10 FEET SOUTH OF UTILITY POLE.	X		
		A	W13-1P	18	18			2.25																		X		
NB	3.558	C	VR-017	24	30		LEGAL LOAD 24K			1				X												N POWNAL RD (TH-2)			
							SHEET TOTALS	36.75	0.00	~~2~~ 1	0	0	~~8~~ 7	0	0	4		~~45.0~~ 60.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	224.3	0.0	~~31~~ 28	~~3~~ 0	~~3~~ 0	~~47~~ 44	0	0	~~32~~ 31		~~480.0~~ 465.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118** PLOT DATE: **2/15/2013**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED **A. GAMBLE**
POWNAL NB SHEET 5 SHEET **82** OF **97**