DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POWNAL VT-346 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	4.628	F	VR-039	24	12		STATE HIGHWAY BEGINS						1		X														
		E	VR-038	24	12		STATE HIGHWAY ENDS						1																
		F	VD-700	6	10		3460 0208 0470				1																		
		F	R2-1	24	30								1																
		F	VW16-18P	24	12	FY	STATE LAW	2.00								1		15'-6" X										6	
		F	R2-1	24	30		SPEED LIMIT 50 UNLESS OTHERWISE POSTED	5.00																			X		
		F	VD-700	6	10		MILE MARKER					1																	
		F	R2-5P	24	18			3.00																			X		
SB	4.628	F	VR-039	24	12		STATE HIGHWAY BEGINS	3.00								1		15'-4" X								INSTALL BACK TO BACK SIGN ASSEMBLY TO THE RIGHT OF THE SPEED LIMIT 50 SIGN ASSEMLBY.		6	
		E	VR-038	24	12		STATE HIGHWAY ENDS	3.00																				6	
SB	4.595	F	VW-619	30	30		SHOULDER NARROWS						1		X														
		F	VD-421	60	48		Welcome To VERMONT	20.00								2			11'-0" 12'-0" X							INSTALL AT SOUTH END OF BRIDGE BEHIND RAIL.		5	
SB	4.557	F	VD-421A	60	48		WELCOME TO VERMONT						1		X														
		F	VW-619	36	36		SHOULDER NARROWS	9.00								2		15'-0" 13'-8" X										7	
SB	4.502	F	W3-5	36	36								1		X														
		F	W3-5	36	36		SPEED LIMIT 40	9.00								2		13'-11" 14'-3" X									X		
SB	4.465	F	W10-1	36	36								1		X														
							SHEET TOTALS	54.00	0.00	0	~~0~~ 1	~~0~~ 1	7	0	0	8		120.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	~~339.8~~ 346.1	0.0	~~32~~ 33	~~0~~ 5	~~0~~ 5	~~66~~ 72	0	0	~~28~~ 30		~~420.0~~ 450.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(41)

FILE NAME: 12C118
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
POWNAL SB SHEET 1

PLOT DATE: 2/13/2013
DRAWN BY: J. KELLY
CHECKED A. GAMBLE