DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POWNAL VT-346 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	VD1-1A	72	12			6.00																		INSTALL NEW ON EXISTING FLANGED CHANNEL SIGN POSTS.		10	
SB	3.588	F	OM-3R	12	36								1	X															
		F	OM3-R	12	36			3.00																		INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.	X		
SB	3.580	E	OM-3L	12	36								1	X															
		E	OM3-L	12	36			3.00																		INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.	X		
SB	3.534	F	M3-3	24	12								1	X															
		F	M1-5	30	24								1																
		F	M3-3	24	12			2.00																		INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.			E-136B
		F	M1-5	30	24			5.00																					E-136B
		F	VD-700	6	10		3460 0208 0340				1																		
SB	3.419	F	VW-622	30	30								1		X														
		F	VD-700	6	10							1																	
		F	VW-622	30	30			6.25								1		11'-0" X										7	
SB	3.342	F	R2-1	24	30								1	X															
		F	R2-1	24	30			5.00																		INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.	X		
		F	VD-700	6	10		3460 0208 0320				1																		
SB	3.233	F	W11-8	30	30								1	~~X~~	X														
		F	VD-700	6	10							1																	
		F	W11-8	30	30			6.25								1		15'-0" X										~~INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.~~	X		
SIGN SUMMARY SHEET							SHEET TOTALS	36.50	0.00	0	~~2~~ ~~0~~	~~2~~ ~~0~~	7	0	0	~~2~~ ~~1~~		~~30.0~~ ~~15.0~~			0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT			EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	346.1 ~~339.8~~	0.0	33 ~~32~~	~~5~~ ~~0~~	~~5~~ ~~0~~	~~72~~ ~~66~~	0	0	~~30~~ ~~28~~		~~450.0~~ ~~420.0~~			0	0.0						

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
POWNAL SB SHEET 4

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **89** OF **97**