DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POWNAL VT-346 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	0.648	F	R2-1	30	36		SPEED LIMIT 35			1				X															
SB	0.564	F	W1-1L	30	30		LEFT TURN			1				X															
		F	W13-1	18	18		20 MPH ADVISORY						1													REMOVE 20 MPH ADVISORY			
		F	W13-1P	18	18		15 MPH	2.25																		INSTALL NEW 15 MPH ADVISORY.	X		
SB	0.503	F	R8-3A	24	24		NO PARKING			1				X															
SB	0.492	E	M3-1	24	12		ROUTE MARKER ASSEMBLY.			1				X															
SB	0.492	E	M1-5	30	24					1																			
SB	0.492	E	M6-1	21	15					1																			
SB	0.490	E	W1-6	48	24		LARGE RIGHT ARROW			1				X															
SB	0.489	G	VR-017	24	30								1	X													MAIN STREET (TH-8)		
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																		INSTALL NEW SIGN ON EXISTING FLANGED CHANNEL SIGN POST.		6
SB	0.485	F	D3-1	UNK	UNK								1													MAIN STREET (TH-8)		
		G	VD-700	6	10		3460 0208 0048			1																		
		H	R1-1	30	30								1	X															
		F	D3-1	30	12		Main st	2.50																		INSTALL STREET NAME SIGN ABOVE STOP SIGN AND ON EXISTING POST.		12
		H	R1-1	30	30		STOP	6.25																			X		
							SHEET TOTALS	16.00	0.00	~~8~~ 7	0	0	4	0	0	0	0.0				0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT				EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	346.1 ~~339.8~~	0.0	~~33~~ ~~32~~	~~5~~ ~~0~~	~~5~~ ~~0~~	~~72~~ ~~66~~	0	0	~~30~~ ~~28~~	~~450.0~~ ~~420.0~~				0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
POWNAL SB SHEET 7

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **92** OF **97**