DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POWNAL VT-346 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	0.484	G	VR-017	24	30								1	X												CHURCH ST (TH-1)			
		G	VR-017	24	30			5.00																		INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.		6	
SB	0.483	H	R1-1	30	30								1	X												CHURCH ST (TH-1)			
		F	D3-1	38	12			3.17																		INSTALL ABOVE STOP SIGN.		12	
		H	R1-1	30	30			6.25																		INSTALL ON EXISTING FLANGED CHANNEL SIGN POST.	X		
SB	0.483	F	D3-1	UNK	UNK		CHURCH ST STREET NAME SIGN						1		X														
SB	0.482	F	W1-6	48	24		LARGE LEFT ARROW			1				X															
SB	0.481	F	M3-3	24	12		SOUTH			1				X															
		F	M1-5	30	24		VERMONT ROUTE 346			1																			
		F	M6-1	21	15		LEFT ARROW			1																			
SB	0.456	F	M3-3	24	12		SOUTH			1				X															
		F	M1-5	30	24		VERMONT ROUTE 346			1																			
SB	0.410	F	R8-3A	24	24		NO PARKING			1				X															
SB	0.355	F	W1-4R	30	30		RIGHT REVERSE CURVE						1		X														
		F	W11-8	30	30								1																
							SHEET TOTALS	14.42 SF	0.00 SF	7 EA	0 EA	0 EA	5 EA	0 EA	0 EA	0 EA		0.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	~~339.8~~ 346.1	0.0	~~32~~ 33	~~0~~ 5	~~0~~ 5	~~66~~ 72	0	0	~~28~~ 30		~~420.0~~ 450.0		0	0.0							

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**

FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
POWNAL SB SHEET 8

PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **93** OF **97**