DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
POWNAL VT-346 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	M1-4	24	24								1															
		F	M6-1	21	15								1					14'-2" 14'-5"										
		F	M3-1	24	12			2.00																		INSTALL SIGNS ON EXISTING SIGN FRAME AND FLANGED CHANNEL SIGN POSTS.	X		
		F	M1-4	24	24			4.00																			X	
		F	M6-1L	21	15			2.19																			X	
		F	M3-3	24	12			2.00																			X	
		F	M1-4	24	24			4.00																			X	
		F	M6-1R	21	15			2.19																			X	
SB	0.033	F	R8-3A	24	30		NO PARKING			1				X														
SB	0.033	F	M4-6P	24	12		END			1																		
SB	0.021	F	VR-656	24	30								1		X													
		F	VR-656	24	30		DO NOT BLOCK DRIVE	5.00								1		12'-0" X									6	
SB	0.018	~~G~~ ~~F~~	R1-1	30	30								1	X														
		~~G~~ ~~F~~	R1-1	30	30		STOP	6.25																		INSTALL ON EXISTING SIGN POST.	X		
SB	0.000	F	R1-1	30	30		STOP						1	X												INSTALL ON EXISTING POST	X		
		F	R1-1	30	30			6.25																				
SIGN SUMMARY SHEET							SHEET TOTALS	~~33.88~~ ~~27.63~~	0.00	2	0	0	~~5~~ ~~4~~	0	0	1		15.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	~~346.1~~ ~~339.8~~	0.0	~~33~~ ~~32~~	~~5~~ ~~0~~	~~5~~ ~~0~~	~~72~~ ~~66~~	0	0	~~30~~ ~~28~~		~~450.0~~ ~~420.0~~		0	0.0								

PROJECT NAME: **STATEWIDE SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(41)**
FILE NAME: **12C118**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
POWNAL SB SHEET 11
PLOT DATE: **2/13/2013**
DRAWN BY: **J. KELLY**
CHECKED **A. GAMBLE**
SHEET **96** OF **97**