



RAIL LAYOUT

SCALE: 1' = 10'-0"

NOTE: ALL DIMENSIONS ARE MEASURED HORIZONTALLY ALONG FACE OF RAIL.

SPECIAL PROVISION (BOX BEAM GUARDRAIL W/ 7 FEET POSTS) (COATED DARK GREEN)

STA 144+19.00 RT - 144+82.00 RT
 STA 144+28.74 LT - 145+16.60 LT
 STA 146+05.38 RT - 146+09.29 RT APPROACH SECTION
 STA 146+71.10 LT - 147+01.02 LT

SPECIAL PROVISION (GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING) (COATED DARK GREEN)

STA 144+82.00 RT - 145+16.00 RT
 STA 145+16.60 LT - 145+50.60 LT
 STA 146+02.50 RT - 146+09.29 RT
 STA 146+37.10 LT - 146+71.10 LT

SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED METAL HAND RAILING/CONCRETE PARAPET COMBINATION) (COATED DARK GREEN)

STA. 145+16.00 RT - 146+02.50 RT
 STA. 145+50.60 LT - 146+37.10 LT

MANUFACTURED TERMINAL SECTION, TANGENT (COATED DARK GREEN)

STA 144+04.99 RT - 144+19.00 RT

NOTES:

1. STEEL COMPONENTS OF THE BOX BEAM GUARDRAIL, APPROACH RAILING, BRIDGE RAILING, AND MANUFACTURED TERMINAL SECTION SHALL BE POWDER COATED DARK GREEN, CLOSELY MATCHING FEDERAL COLOR CHIP NUMBER 14062, IN ACCORDANCE WITH ASTM D7803 FOLLOWING GALVANIZING. PAYMENT WILL BE MADE UNDER THE APPROPRIATE RAILING ITEM.
2. PROVIDE GUARDRAIL TERMINAL LABELS IN ACCORDANCE WITH HSD-621.06.

TYLIN INTERNATIONAL	PROJECT NAME: CHelsea	PLOT DATE: 8/31/2016
	PROJECT NUMBER: BHF 0169(9)	DRAWN BY: S. MORGAN
	FILE NAME: z12ci50ralllay.dgn	CHECKED BY: J. HOWE
	DESIGNED BY: B. TOOTHAKER	SHEET 30 OF 137
	RAIL LAYOUT SHEET	