

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		EACH	RELOCATE HYDRANT	629.29				
						80				80		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						840				840		HR	FLAGGERS	630.15				
									0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
									0.5	0.5		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						0.5				0.5		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						4				4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						840				840		LF	4 INCH WHITE LINE	646.20				
						700				700		LF	4 INCH YELLOW LINE	646.21				
						6				6		EACH	LETTER OR SYMBOL	646.30				
						56				56		LF	CROSSWALK MARKING	646.31				
						1050				1050		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
								465		465		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							320			320		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							174			174		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							24			24		LB	SEED	651.15				
							5			5		LB	SEED, WINTER RYE	651.17				
							148			148		LB	FERTILIZER	651.18				
							0.6			0.6		TON	AGRICULTURAL LIMESTONE	651.20				
							0.6			0.6		TON	HAY MULCH	651.25				
						39				39		CY	TOPSOIL	651.35				
						21		115		136		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN (BRIDGE 11)	652.10				
							10			10		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BRIDGE 11)	652.30				
							114			114		SY	TEMPORARY EROSION MATTING	653.20				
							33			33		CY	VEHICLE TRACKING PAD	653.35				
							1			1		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
							730			730		LF	PROJECT DEMARCATION FENCE	653.55				
						2				2		LS	TREE PROTECTION	656.85				
						36.63				36.63		SF	TRAFFIC SIGNS, TYPE A	675.20				
						134				134		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						15				15		EACH	REMOVING SIGNS	675.50				
						8				8		EACH	ERECTING SALVAGED SIGNS	675.60				
						1				1		EACH	DELINEATOR WITH STEEL POST	676.10				
						285				285		LF	WIRED CONDUIT (1") (PVC)	678.23				
						2				2		EACH	JUNCTION BOX	678.26				
						1				1		EACH	POWER DROP STANCHION, STREET LIGHTING	679.55				

PROJECT NAME: CHELSEA  
 PROJECT NUMBER: BHF 0169(10)  
 FILE NAME: z12ci52q+y.dgn  
 PROJECT LEADER: J. OLUND  
 DESIGNED BY: D. MYERS  
 QUANTITY SHEET 2  
 PLOT DATE: 10/4/2016  
 DRAWN BY: D. MYERS  
 CHECKED BY: B. TOOTHAKER  
 SHEET 82 OF 137

