TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																						REMARKS	SIGN DETAIL	
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POST	FLANGED CHANNEL (LB / FT) 1	2	3	SQUARE STEEL (in) (LB / FT) 1.75 1.88	2.00 2.42	2.50 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) (LB / FT) 3.00 1.30	4.00 1.70	4.0 MOD 1.70	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 7.60	3.50 9.00	4.00 10.80	5.00 14.60	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
OPTION ITEMS																																		
168+00, RT									1																								RETAIN EXISTING SIGN		
		1	24	8	1.33																												STANDARD HIGHWAY SIGNS AND MARKINGS S4-3P; INSTALL BELOW RETAINED SIGN ON EXISTING POST; FLOURESCENT YELLOW GREEN		
172+99, RT		1	30	30	6.25						1				15.0			1															STANDARD HIGHWAY SIGNS AND MARKINGS S1-1; FLOURESCENT YELLOW GREEN		
		1	21	15	2.19																												STANDARD HIGHWAY SIGNS AND MARKINGS W16-7P; FLOURESCENT YELLOW GREEN		
173+07, LT		1	30	30	6.25						1				15.0			1															STANDARD HIGHWAY SIGNS AND MARKINGS S1-1; FLOURESCENT YELLOW GREEN		
		1	21	15	2.19																												STANDARD HIGHWAY SIGNS AND MARKINGS W16-7P; FLOURESCENT YELLOW GREEN		
175+90, RT		1	72	12			1				2				30.0			2																	
		1	72	12			1																													
		1	24	12			1																													
		1	30	24			1																													
176+00, RT		1	6	10	0.42						1				7.0			1																	T-42
176+52, LT		1	6	10	0.42						1				7.0			1																	T-42
177+36, RT		1	24	30	5.00						1				15.0			1																STANDARD HIGHWAY SIGNS AND MARKINGS R2-1: BLACK ON WHITE		
177+36, RT		1	24	12			1				1				15.0			1																	
		1	24	24			1																													
177+55, LT		1	24.0	30.0	5.00						1				15.0			1																STANDARD HIGHWAY SIGNS AND MARKINGS R2-1: BLACK ON WHITE		
												FT 0	FT 0	FT 0	FT .	FT 119.	FT .	XXXXX XXXXX XXXXX XXXXX	EA 0	LB .	LB .	LB .		LB .	LB .	LB .	LB .						
	SUBTOTAL	SF 29.05	SF .	EA. 6	SF 0	XXXXXXXXXX XXXXXXXXXX XXXXXXXXXX						FT 0			FT 119.					LB .			EA.	LB .				EA. .							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TYLIN INTERNATIONAL

PROJECT NAME: CHELSEA
PROJECT NUMBER: BHF 0169(10)

FILE NAME: z12c152sgnsum.dgn
PROJECT LEADER: J. OLUND
DESIGNED BY: B. TOOTHAKER
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 8/31/2016
DRAWN BY: B. TOOTHAKER
CHECKED BY: D. BRYANT
SHEET 93 OF 137