TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																								REMARKS	SIGN DETAIL	
											NO. OF	FLANGED CHANNEL			SQUARE STEEL (in)					TUBULAR ALUMINUM Ø (IN)			TUBULAR STEEL Ø (IN)					W-SHAPE STEEL									DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	POST	(LB / FT)			1.75 (LB / FT)	2.00 (LB / FT)	2.50 (LB / FT)	ANCHOR	SLEEVE	3.00 (LB / FT)	4.00 (LB / FT)	4.0 MOD (LB / FT)	FOUNDATION	3.00 (LB / FT)	3.50 (LB / FT)	4.00 (LB / FT)	5.00 (LB / FT)	FTG. SIZE 24"	FTG. SIZE 30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED				
												1.12	2.00	3.00	1.88	2.42	3.35			1.30	1.70	1.70		7.60	9.00	10.80	14.60								
OPTION ITEMS																																					
177+55, LT		1	24.0	12.0			1				1					15.0		1																			
		1	24.0	24.0			1																														
178+80, LT		1	30	30	6.25				1																										STANDARD HIGHWAY SIGNS AND MARKINGS S1-1; FLOURESCENT YELLOW GREEN		
		1	24	8	1.33																													STANDARD HIGHWAY SIGNS AND MARKINGS S4-3P; FLOURESCENT YELLOW GREEN		
SUBTOTAL		SF 7.58	SF .	EA. 2.	SF .	XXXXXXXXXX XXXXXXXXXX XXXXXXXXXX					FT .	FT .	FT .	FT .	FT 15.	FT .	XXXXX XXXXX XXXXX XXXXX	EA .	LB .	LB .	LB .		LB .	LB .	LB .	LB .									
GRAND TOTALS		SF 36.63	SF .	EA. 8.	SF .	XXXXXXXXXX XXXXXXXXXX XXXXXXXXXX					FT .			FT 134.					LB .			EA.	LB .				EA. .									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TYLIN INTERNATIONAL

PROJECT NAME: CHELSEA
PROJECT NUMBER: BHF 0169(10)

FILE NAME: zl2cl52sgnsum.dgn
PROJECT LEADER: J. OLUND
DESIGNED BY: B. TOOTHAKER
TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 8/31/2016
DRAWN BY: B. TOOTHAKER
CHECKED BY: D. BRYANT
SHEET 94 OF 137