STATE OF VERMONT
AGENCY OF TRANSPORTATION

DRAINAGE DETAIL SHEET

STATION	STATION	POS.	ASKEW	INLET/OUTLET TYPE		DITCH		PIPE ARCH			PIPE		ALLOWABLE OPTIONS						PIPE ELBOW	ES	CB		DEPTH DI	CONC CLASS B	REINF STEEL	DI GRATE	CHAN ELEV	CRM	TRENCH EXCAVATION		COMM EXC	UNC CHAN EXC	STRUCT EXCAV	GRAN BKFILL STRUCT	GRAN BORR	EROS MATT	STONE FILL		MARKER POSTS				REMARKS
				INLET	OUTLET	IN	OUT	SPAN	RISE	L	D	L	PCCSP	CAAP	RCP	CSP	CPEP	PCCSP PI											EARTH	ROCK									LT	RT			
			NO. DEG.					IN	IN	FT	IN	FT	TH	TH	CL	TH	SL	TH	NO. DEG.	EA	EA		FT	CY	LBS	TYPE	EA	CY	CY	CY	CY	CY	CY	CY	CY	SY	CY	TYPE	EA	EA			
326+87.58	326+93.36	LT-RT	84.6 RT	PIPE	PIPE						48	62	X																84					84					1	1			DRAINAGE NOTE #1 - ADD INLET PROTECTION
328+63.30	328+70.00	LT-RT	82.9 RT	PIPE	PIPE						24	54					X												46					46					1	1			DRAINAGE NOTE #2 - ADD INLET/OUTLET PROTECTION
334+65.58	334+77.45	RT-LT	80.5 LT	PIPE	PIPE						36	72					X												120					120					1	1			DRAINAGE NOTE #3 - ADD INLET PROTECTION
338+50.75	338+50.75	RT-LT	90	PIPE	PIPE						30	56					X												53					53					1	1			DRAINAGE NOTE #4 - ADD INLET PROTECTION
341+51.13	341+52.08	RT-LT	83.9 LT	PIPE	PIPE						24	50					X												39					39					1	1			DRAINAGE NOTE #5 - ADD INLET PROTECTION
326+99.40	327+47.92	RT																											24					24									DRAINAGE NOTE #6 REMOVE EXISTING 15" DRIVE PIPE
TOTALS :																													366					366					5	5			

PROJECT NAME: SHARON
PROJECT NUMBER: ER STP 0147(20)

FILE NAME: z12c410.dgn
PROJECT LEADER: J. TUCKER
DESIGNED BY: B. BRESLEND
DRAINAGE DETAIL SHEET

PLOT DATE: 3/31/2015
DRAWN BY: B. MACK
CHECKED BY: A. SANZ
SHEET 19 OF 66