STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	~~FLANGED CHANNEL~~ REMOVING SIGNS ~~lb/ft~~ ~~1.12~~	~~2.0~~	~~3.0~~	SQUARE STEEL (in) lb/ft 1.75 / 1.88	2.0 / 2.42	2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 / 1.3	4.0 / 1.7	4.0 MOD / 1.7	TUBULAR STEEL Ø (in) lb/ft FOUND-ATION	3.0 / 7.6	3.5 / 9.0	4.0 / 10.8	5.0 / 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. 325+25 RT			30	30			1				1					X 13.0		X															MOUNT SALVAGED SIGN ON POST			
STA. 326+18 RT		1	48	24	8.00						2		1			X 21.0		X															WI-6R			SHSM
STA. 326+28 RT		1	48	24	8.00						2		1			X 22.5		X															WI-6L			SHSM
STA. 327+36 RT		1	6	10	0.42						1		1		X 8.75			X															VD-700			T-44
STA. 331+75 LT		1	30	30	6.25						1					X 13.5		X															WI-2R			SHSM
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BA. SANZED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."		SUBTOTAL	22.67		1							~~LF~~	~~LF~~ 3 EA	~~LF~~	LF ~~10~~ 8.75	LF ~~90~~ 70.0	LF -		EA.	LB	LB	LB		LB	LB	LB	LB								
		ROUNDING	0.33																																	
		TOTALS	SF 23.00	SF	EA.	SF						~~LF~~ 3 EA			LF ~~100~~ 78.75					LB			EA.	LB				EA.	EA.	LB					

PROJECT NAME: SHARON
PROJECT NUMBER: ER STP 0147(20)

FILE NAME: z12c410.dgn
PROJECT LEADER: J. TUCKER
DESIGNED BY: B. BRESLEND
TRAFFIC SIGN SUMMARY SHEET

PLOT DATE: 3/31/2015
DRAWN BY: B. MACK
CHECKED BY: A. SANZ
SHEET 50 OF 66