



MESSAGES FOR PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS) – REGIONAL DETOUR

STARTING 2 WEEKS PRIOR TO CLOSURE

MESSAGE 1	MESSAGE 2
VT 125	MM / DD
ROAD	TO
CLOSED	MM / DD

DURING CLOSURE

MESSAGE 1	MESSAGE 2
VT 125	PIPER BR.
ROAD	AT
CLOSED	SILVER ST.

ID NUMBER	SIGN TEXT	SIZE OF SIGN WIDTH HEIGHT	NUMBER OF SIGNS REQ'D.	AREA OF EACH SIGN (SF)	COLOR	REMARKS
W20-2	DETOUR AHEAD	48" 48"	5	16.00	B/F/O	INSTALL ON 2 POSTS
W20-3	ROAD CLOSED 1000 FT	48" 48"	2	16.00	B/F/O	INSTALL ON 2 POSTS
M6-3	↑	21" 15"	3	2.19	B/F/O	MOUNT BELOW VMI-5
M6-1R	→	21" 15"	5	2.19	B/F/O	MOUNT BELOW VMI-5
M6-1L	←	21" 15"	5	2.19	B/F/O	MOUNT BELOW VMI-5
M5-1L	↙	21" 15"	4	2.19	B/F/O	MOUNT BELOW VMI-5
M5-1R	↘	21" 15"	5	2.19	B/F/O	MOUNT BELOW VMI-5
M6-2R	↗	21" 15"	1	2.19	B/F/O	MOUNT BELOW VMI-5
M4-8	DETOUR	24" 12"	91	2.00	B/F/O	MOUNT ABOVE M3-2 OR M3-4
M4-8A	END DETOUR	24" 18"	2	3.00	B/F/O	MOUNT ABOVE M3-2 OR M3-4
M3-2	EAST	24" 12"	52	2.00	G/W	MOUNT ABOVE VMI-5
M3-4	WEST	24" 12"	41	2.00	G/W	MOUNT ABOVE VMI-5
VMI-5	VERMONT 125	30" 24"	93	5.00	G/W	
R11-2	ROAD CLOSED	48" 30"	2	10.00	B/W	INSTALL ON 2 POSTS
R11-3B	ROAD CLOSED XX MILES AHEAD NO THRU TRAFFIC	60" 30"	2	12.5	B/W	INSTALL ON TYPE III BARRICADES

B/F/O = BLACK ON FLUORESCENT ORANGE BACKGROUND
G/W = RETROREFLECTIVE GREEN ON RETROREFLECTIVE WHITE BACKGROUND
B/W = BLACK ON RETROREFLECTIVE WHITE BACKGROUND

PROJECT NAME: HANCOCK
PROJECT NUMBER: ER STP 0174(18)
FILE NAME: z12c412detour.dgn
PROJECT LEADER: J. TUCKER
DESIGNED BY: B. BRESLEND
DETOUR DETAIL SHEET 2
PLOT DATE: 10/11/2016
DRAWN BY: O. DALMER
CHECKED BY: A. SANZ
SHEET 42 OF 42