DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ORWELL VT-73 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	0.544	A	VW-202	30	30		TRUCKS ENTERING						1		X													
EB	0.562	A	W11-10	30	30			6.25								1		15.0 X								INSTALL 190 FT EAST OF EXISTING	X		
EB	0.628	A	R2-1	24	30		SPEED LIMIT 35						1		X													
		A	W11-8	30	30			6.25								1		16.0 X								INSTALL AT LOCATION OF EXISTING SPEED LIMIT	X		
EB	0.671	A	W1-2L	30	30		LEFT CURVE						1		X													
EB	0.857	A	W1-2L	30	30		LEFT CURVE						1	X														
		A	VW-060	30	30								1															
		A	VW-060	30	30			6.25																	TRIM ADDITIONAL POST HEIGHT NOT REQUIRED FOR SINGLE SIGN INSTALLATION		9	
EB	0.892	A	R2-1	24	30		SPEED LIMIT 50						1		X													
		A	R2-1	24	30			5.00								1		13.75 X									X		
EB	1.434	A/B	D3-1	UNK.	UNK.		RAYMOND HILL RD (TH-5)			NO SIGN FOUND ~~1~~		~~1~~	~~1~~	X		1		~~X~~								INSTALL ADDITIONAL POST AND REMOUNT SIGN TO BOTH POSTS			
EB	1.434	C	VR-017	24	30								1	X														
		C	VR-017	24	30			5.00																	RAYMOND HILL RD (TH-5)		9	
EB	1.443	D	R1-1	30	30								1	X													EXISTING POST WAS DAMAGED			
		D	R1-1	30	30			6.25								1		13.75 X								RAYMOND HILL RD (TH-5)	X		
SIGN SUMMARY SHEET							SHEET TOTALS	35.00	0.00	0	~~0~~ 1	~~0~~ 1	~~8~~ 9	0	0	~~5~~ 4		~~58.5~~ 60.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	285.3	0.0	1	3	3	56	0	0	35		525.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTHWEST**
PROJECT NUMBER: **STPG SIGN(47)**

FILE NAME: **z12c534TSS.xlsm**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **B. TOOTHAKER**
ORWELL EB SHEET 4

PLOT DATE: **9/12/2014**
DRAWN BY: **B. TOOTHAKER**
CHECKED **K. KERN**
SHEET **17** OF **107**