DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ORWELL VT-73 EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
EB	1.794	A	W2-2ML	30	30								1	X															
		A	W2-2L	30	30			6.25																			X		
EB	1.834	A	S3-1T	30	30		SCHOOL BUS STOP AHEAD						1		X														
EB	2.056	A/B	D3-1	UNK.	UNK.								1		X														
		A/B	D3-1	66	12			5.50								2		12.0 X 12.0									11	
EB	2.187	A	W1-2R	30	30			6.25								1		15.5 X								INSTALL 200 FT WEST OF EXISTING HIDDEN DRIVE RIGHT	X		
EB	2.225	A	VW-054R	30	30								1	X												EXISTING POST WAS DAMAGED			
		A	VW-133R	30	30			6.25								I		14.0 X									9	
EB	2.688	A/B	D3-1	UNK.	UNK.								1		X														
		A/B	D3-1	42	12			3.50								1		11.5 X									11	
EB	2.978	A	VD-062AL	72	16		BUSINESS SIGN			1				X															
EB	3.021	A	W13-1	18	18		30 MPH						1		X														
		A	W1-2R	30	30		RIGHT CURVE						1																
EB	3.045	A	W1-4R	30	30			6.25								1		17.0 X								INSTALL 125FT EAST OF EXISTING	X		
		A	W13-1P	18	18			2.25								I											X		
SIGN SUMMARY SHEET							SHEET TOTALS	36.25 SF	0.00 SF	1 EA	0 EA	0 EA	7 EA	0 EA	0 EA	~~6~~ 5 EA		~~82.0~~ 75.0 FT			0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	285.3	0.0	1	3	3	56	0	0	35		525.0			0	0.0							

PROJECT NAME: STATEWIDE-SOUTHWEST
PROJECT NUMBER: STPG SIGN(47)
FILE NAME: z12c534TSS.xlsm
PROJECT MANAGER: D. BRYANT
DESIGNED BY: B. TOOTHAKER
PLOT DATE: 9/12/2014
DRAWN BY: B. TOOTHAKER
CHECKED K. KERN
ORWELL EB SHEET 5